

#### THREE RIVERS SOUTHEAST ARKANSAS

#### Introduction

The Three Rivers Southeast Arkansas Feasibility Study (Three Rivers Study) is being conducted by the U. S. Army Corps of Engineers (USACE) to recommend modifications to the McClellan-Kerr Arkansas River Navigation System (MKARNS) that would provide long-term sustainable navigation and promote the continued safe and reliable economic use of the MKARNS.

#### **Study Authority**

Section 216, Flood Control Act of 1970 (Public Law 91-611) authorizes a feasibility study due to examine significantly changed physical and economic conditions in the Three Rivers study area. The study will evaluate and recommend modifications for long-term sustainable navigation on the MKARNS.

#### **Study Purpose**

There is a risk of a breach of the existing Soil Cement Structure near the entrance channel to the MKARNS on the White River. During high water events, Mississippi backwater can create significant head differentials between the Arkansas and White rivers. The existing Soil Cement Structure in the isthmus between the Arkansas and White rivers is subject to damaging overtopping, flanking and seepage flows that could result in a catastrophic breach and failure of the system. The uninhibited development of a breach, or cutoff, has the potential to create navigation hazards, increase the need for dredging, and adversely impact an estimated 200 acres of bottomland hardwood forest in the isthmus.

Based on the Section 216 authority, the study is investigating alternatives that would minimize the risk of cut off development, including reducing the cost of maintence associated with preventing cutoff development, while minimizing impacts to the surrounding ecosystem.

#### Non-Federal Sponsor

The Arkansas Waterways Commission is the non-federal sponsor for the Three Rivers Southeast Arkansas Study. An amended feasibility cost-sharing agreement was executed in June 2015.

#### **Recommended Plan**

The recommended plan consists of a newly constructed 2.5-mile long containment structure at an elevation of 157 feet above mean sea level (ft msl) that would begin on natural high ground just south and west of the existing Melinda Structure located on the south side of Owens Lake. It would continue east and cross the Melinda head cut south of the existing Melinda Structure. From there, it would head northeast and connect to the existing Soil Cement Structure north of Jim Smith Lake. It continues to follow the existing Soil Cement Structure alignment terminating at the existing Historic Closure Structure. The recommended plan also includes a relief opening at the Historic Cutoff to an elevation 145 ft msl regardless of the width. In addition, the existing Melinda Structure would be demolished in place and the debris would be pushed into the deep scour hole at the top of the head cut. Finally, adding an opening in the existing Owens Lake Structure between Owens Lake and the White River would prevent water from backing up into Owens Lake, which would impact the bottomland hardwood forest. The opening would be designed to allow fish passage into Owens Lake.

### **Table of Contents**

1.	GENERAL	3
2.	HYDROLOGY AND HYDRAULICS (H&H)	5
3.	SURVEYING, MAPPING AND OTHER GEOSPATIAL DATA REQUIREMENTS	5
4.	GEOTECHNICAL	6
5.	ENVIRONMENTAL ENGINEERING	7
6.	CIVIL DESIGN	7
6.	1.1 No Action Plan	7
	1.2 Alternative 1 – Stone Containment Structure at Elevation 157 and Re-opening e Historic Cutoff (Tentatively Selected Plan (TSP))	•
6.	1.3 Alternative 2 – Multiple Openings	.11
	1.4 Environmental Alternatives	
	STRUCTURAL REQUIREMENTS	
	ELECTRICAL AND MECHANICAL REQUIREMENTS	
9.	HAZARDOUS AND TOXIC MATERIALS	.16
10.	CONSTRUCTION PROCEDURES AND WATER CONTROL PLAN	
11.	INITIAL RESERVOIR FILLING AND SURVEILLANCE PLAN	.16
12. OF (	FLOOD EMERGENCY PLANS FOR AREAS DOWNSTREAM AND UPSTREAL CORPS DAMS	
13.	ENVIRONMENTAL OBJECTIVE AND REQUIREMENTS	
14.	RESERVOIR CLEANING	.17
15.	OPERATION AND MAINTENANCE	.17
16.	ACCESS ROADS	.17
17.	CORROSION MITIGATION	18
18.	PROJECT SECURITY	18
19.	COST ESTIMATES	.19
20.	SCHEDULE FOR DESIGN AND CONSTRUCTION	.19
21.	SPECIAL STUDIES	.19
22.	PLATES, FIGURES AND DRAWINGS	.19
23.	DATA MANAGEMENT	.19
24.	USE OF METRIC SYSTEM MEASUREMENTS	.19
25. BUN	REPORT ON DESIGN AND CONSTRUCTION DEFICIENCIES IN THE DALE MPERS WHITE RIVER NATIONAL WILDLIFE REFUGE, ARKANSAS	. 19
26.	ATTACHMENT A	21

Pl	ates, Figures and Drawings	21
	ATTACHMENT B	
Ro	ock Gradation for the Proposed Weir through the Historic Cutoff Structure	. 35
28.	ATTACHMENT C	. 36
	eport on Design and Construction Deficiencies in the Dale Bumpers White River ational Wildlife Refuge, Arkansas	
29.	ATTACHMENT D	. 37
Re	eferenced Drawings	. 37

#### 1. GENERAL

The project area being studied consists of a region where the White River, Arkansas River, Mississippi River and the McClellan-Kerr Arkansas River Navigation System (MKARNS) all interact during flood events to cause it to be a very dynamic area. When the Mississippi River is at flood stage it backs up the White River and eventually reaches a level where the White River's flow cannot stay within the banks. When this occurs it flows overland towards the Arkansas River, causing erosion to occur on a massive scale. Over time multiple headcuts have formed and were ultimately closed by the Corps of Engineers before significant damage could occur. The Owens Lake Structure, The La Grues Lake Structure, the Melinda Structure, the Historic Cutoff Structure, the Jim Smith Structure and the Soil Cement Structure are just some of the facilities that USACE has built over the years in an attempt to control where and how water flows within the area. On a less frequent basis the Arkansas River can also flow towards the White River when it is experiencing a flooding condition. If the White River were to create a new channel to the Arkansas River, navigation utilizing the MKARNS would be disrupted. This is especially true of the barge shipping industry that uses the MKARNS to ship billions of dollars of commodities. The H&H Appendix discusses further how a breach in the study area would disrupt navigation.


The goals for this project are to reduce the potential risk of a catastrophic breach, to ensure that navigation can continue on the MKARNS and that environmental impact is limited. The means for achieving each of these goals is to reduce the damaging velocity heads which are causing the erosive forces creating new channels between the White River and the Arkansas River. This in turn will prevent disruption of river navigation and prevent destruction of the surrounding woodland areas. In order to do this, construction of various structures will need to be completed.

The engineering designs to follow were prepared to provide structures that are resilient enough to withstand the hydraulic forces that the Three Rivers system is capable of producing. Should the structures require any maintenance or repairs, they can be easily performed with conventional construction equipment and the various stone materials required.

All the proposed structures will be hardened utilizing stone that has been delivered to the project site by the Sponsors shippers, utilizing the MKARNS.

On the next page is the Three Rivers Structure Map. It will provide the reader of this document the location of the existing structures located within the project area that will be impacted by the proposed projects to be discussed later in the Engineering Appendix.

### THREE RIVERS STRUCTURE MAP



#### 2. HYDROLOGY AND HYDRAULICS (H&H)

H&H personnel performed numerous computer models to come up with the Alternatives that have been designed for this appendix. The complete H&H analysis is covered in a separate appendix and will provide a full explanation of the modeling that was performed.

The team investigated climate change impacts per "Guidance for Incorporating Climate Change Impacts to Inland Hydrology in Civil Works Studies, Designs, and Projects" was issued in Engineering and Construction Bulletin (ECB) 2014-10. The proposed construction improvements are located at an elevation greater than 100 feet above Mean Sea Level and will not be impacted by sea level change. Change in climate is not expected to significantly alter the hydrologic analysis for the region and as a result was not specifically modeled for in the project. No climate change impacts have been included in the study.

#### 3. SURVEYING, MAPPING AND OTHER GEOSPATIAL DATA REQUIREMENTS

Where available, LIDAR and hydrographic topographic data were used in the preparation of the designs described in this section. It should be noted that the available LIDAR data was limited in some areas due to high water conditions at the time the LIDAR data was obtained. During the Preconstruction, Engineering and Design (PED) phase, a comprehensive topographic and hydrographic survey will be required in order to develop the formal plans and specifications for construction. This proposed survey will identify topographic features, boundary lines, easements, structures, roads and utility lines, etc.

The available LIDAR and hydrographic topographic data was used within the Bentley INROADS software program to create 3D surface models of the proposed structures. The 3D surface and structure models were used to develop quantities used in the preparation of the cost estimates. These surfaces can create contour data as a byproduct of the computation process but contours are not needed to create quantities, the volume quantities were obtained from comparing the existing and proposed surfaces. The data used provided a realistic basis for the quantities used in the cost estimates.

The existing LIDAR topographic data was obtained in 2014 and used the horizontal datum of NAD83 and vertical datum of NAVD88. The hydrographic data was obtained in 2011. However, no information is available as to how the hydrographic data was obtained or which horizontal and vertical datums were used.

#### 4. GEOTECHNICAL

Sufficient geotechnical information is known about the areas where the proposed structures are to be located. The construction of the stone containment structure will be done by placement of the stone within a 2 foot keyway excavation and filling to the required grade. Based upon visual observation of excavated and eroded areas, the soils under the stone containment structure consist of silty-clay topsoil overlaying sandy materials. These soils have proven to be very stable when flooded and during construction activities. Prior to Preconstruction, Engineering and Design (PED) work, it is recommended that a thorough subsurface exploration must be performed along the proposed route of the Stone Containment Structure to verify the soil types present. Laboratory testing on the soils should include grain size and uniformity of the materials. This information will be required in order to confirm the keyway design at the Melinda Headcut Channel, confirm the 2-foot excavation depth along the length of the stone containment structure and determine if a granular or geotextile fabric filter is required.

The existing Historic Cutoff structure as its name implies, is a structure that was built to close the natural cutoff or bypass that allowed water to flow between the White River and the Arkansas River during a flood event. See the "Three Rivers Structure Map" above for the location of the Historic Cutoff Structure. It is a manmade structure and was constructed utilizing dredged material from the White River. The composition of the dredged material was generally sandy with some clays and silts included. This was visually witnessed during its placement by USACE personnel. As such we do not believe that formal geotechnical testing was required for the lowered Historic Cutoff structures design alternatives identified in this study. The associated geotechnical cost was therefore saved.

Prior to Preconstruction, Engineering and Design (PED) work, it is recommended that a thorough subsurface exploration be performed in the Historic Cutoff to confirm the presence of the sandy soils and for the sheet pile design. Borings should also be taken in the previous sinkhole locations. Laboratory testing on the soils should include grain size and uniformity of the materials. These testing results shall be used to look at maximum foreseeable head differential conditions on both the Arkansas and White River sides of the historic cutoff and look at the average and vertical hydraulic gradients considering the grain size and uniformity of the material in order to evaluate the potential for piping. Finite element modeling could be performed to better optimize the design of the sheet piling.

Stone material for the project's various construction activities is readily available from multiple quarries and can be barged directly to a USACE owned staging area adjacent to the Owens Lake Structure.

Additional Geotechnical information for the project area, including earthquake information, can be found in the draft "Arkansas-White River Cutoff Study" dated November 2007.

#### 5. ENVIRONMENTAL ENGINEERING

The Three Rivers Study revealed some ancillary environmental benefits. They include the reduction in the isthmus velocities that promote erosion, preservation of the bottom land hardwood forest's hydrologic condition and re-connection of the Owens Lake oxbow that had been severed by the existing Melinda Structure. The existing Melinda Structure is located two-thirds of the way between the White River and Arkansas River and separates Owens Lake from the Melinda Headcut Channel. The existing Melinda Structure is constructed mainly of a soil cement mixture, with subsequent repairs utilizing concrete. The demolition of the existing Melinda Structure and the disposal of the debris in the 90 foot deep hole in the channel to the south of the structure will create a roughened bottom habit that will be beneficial for fish. See paragraph 6.1.2C for additional information. No other specific environmental features have been included in this study. For further background information see Appendix B – Hydrologic and Hydraulic Analysis and Appendix D - Environmental.

During the study's preliminary design process, we considered using dredged materials from the MKARNS for portions of the containment structure. However, a design that would be considered resilient enough for the rivers hydraulic flows was not identified. This decision was reinforced by the damage that occurred to the Jim (John) Smith Structure in February of 2005. The structure was built with a geotube core overlain with soil and vegetation. See Figure 1-13 in the "Arkansas-White River Cutoff Study", dated November 2007. It was therefore decided to utilize natural quarried stone for the containment structure. Stone is readily available for the project, it is durable and can be quickly modified or repaired if the need should occur.

#### 6. CIVIL DESIGN

#### 6.1.1 No Action Plan

Other than normal Operation, Maintenance, Repair, Replacement and Rehabilitation (OMRR&R) requirements, the No Action Plan does not have any planned major changes to the existing structures maintaining the navigation system. Since 2014, two sinkholes have formed in the existing Historic Cutoff structure and were repaired. To ensure that the structure does not fail in the future, some form of remediation is required. While there may be other methods, this study only considered two methods for remediating future sinkhole issues. The first is to continue filling the sinkholes with a mixture of earth and stone as they occur, with the potential risk for a damaging breach

still present. This is the method currently being used by USACE Operations personal for sinkhole repairs. The second method and the one recommended for this feasibility study is the installation of a sheet pile cutoff wall. The wall would be 5625 feet long and extend from an elevation of 170 at the top of the sheet pile wall to an elevation of 100 at the bottom. The alignment for the sheet piling will follow the top of the existing Historic Cutoff Structure and be located at least 30 feet from the existing soil cement structure located on its top. This will be done to avoid the existing overhead power line and underground fiber optic cable that runs on either side of the soil cement structure. We consider the use of sheet piling to be a conservative and the most realistic method for repairing the sinkholes. For the No Action Plan, the final decision as to the type of repair method to be utilized for the sinkholes will require additional geotechnical study in the future. This falls within the Operation, Maintenance, Repair, Replacement & Rehabilitation (O,M,R,R&R) requirements for the existing Historic Cutoff Structure.

In addition, the draft "Arkansas-White River Cutoff Study", dated November 2007 outlined additional structures that were to be constructed in the future as required to maintain the navigation system.

# 6.1.2 Alternative 1 – Stone Containment Structure at Elevation 157 and Reopening of the Historic Cutoff (Tentatively Selected Plan (TSP))

This alternative is the Tentatively Selected Plan (TSP) and consists of four major elements:

A. The construction of a Stone Containment Structure at an elevation of 157 feet above sea level. The proposed alignment is shown on sheet C-101 and its centerline geometry has been included in Attachment A. The structure between stations 93+00 and 103+00 at the Melinda Headcut Channel will be constructed of Little Rock District, Grade B stone, all other areas of the structure will be constructed of Little Rock District, Grade C stone. The stone gradations are included in Attachment B. The structure will have a 20 foot wide top, with 1:5 side slopes and will be keyed 2 feet into the existing ground surface, which has an elevation ranging from 157 at the ends to 146 at the Historic Cutoff Channel. A keyway will be required on both sides of the Historic Cutoff Channel. The preliminary design is shown on sheet C-501, detail B. Upon completion of the geotechnical study; the depth of the 2-foot keyed excavation, the sizing of the keyway at the Melinda Headcut Channel and whether a granular or geotextile fabric filter will be required under the stone containment structure will need to be verified.

Numerous alternative design materials were considered for the Containment Structure but only stone was determined to have the resiliency and ease of repair necessary for flowing water. See the table of alternative designs considered and not used. Although the all soil cement structure would be resilient, it was removed from consideration because the cost of repairs are high as USACE has experienced in the past. Due to the remote location of the site, the use of stone provides the most hydraulically resilient structure, with the easiest ability to be maintained or repaired.

Alternative Designs	Resiliency
Considered	
& Not Used	
1 Ton retaining wall	No
block core, 1:10 sand	
slopes & stone cap	
Stone core w/1:1.5	No
slopes, 1:10 sand	
slopes & stone cap	
Precast concrete core	No
wall, 1:10 sand slopes	
& stone cap	
Poured concrete wall	No
core, 1:10 sand	
slopes & stone cap	
Soil cement core,	No
1:10 sand slopes &	
stone cap	
Soil cement structure	Yes
in its entirety.	
Sheet pile core, 1:10	No
sand slopes & stone	
cap	

B. The existing soil cement/concrete Owens Lake Structure will be revised to include a flow equalization structure consisting of a precast concrete bridge unit with no wing walls similar to Forterra's "CrownSpan Precast Bridge Unit". See the Forterra sample design in Attachment D. (Note: there are other precast concrete bridge manufacturers that can build a bridge similar to Forterra's. Use of Forterra's bridge in this study is only

for exhibition purposes and does not constitute endorsement.) The inclusion of the bridge will allow for flow between the White River and Owens Lake to allow the water levels to equalize at the same time without the damaging erosive forces which occur when water flows over the Owens Lake Structure. The bridge shall have the following nominal dimensions, a rise of 5 feet and a span of 30 feet. It is assumed that the existing soil cement structure has sufficient bearing capacity to be utilized for the bridge's foundation. However during the Preconstruction, Engineering & Design (PED) phase of the project, it is recommended that additional testing be performed to verify this assumption. Should the testing determine that there is insufficient bearing capacity, then a footing system will be required to support the bridge. The cost of the footing system has been included in the cost estimate for Alternative 1. After installation of the bridge, backfilling of the surrounding trench will be done with concrete to restore the structural integrity of the Owens Lake Structure. A 12 inch thick non-reinforced concrete slab shall cap the bridge. The means for anchoring the new concrete to the existing Owens Lake Structure and the bridge will need to be designed during the PED phase of the project. Design consideration should also be made for preventing water movement between the contact surfaces between the existing soil cement and new concrete and the new concrete and the precast concrete bridge. See sheet C-103 for the structures location.

- C. The existing Melinda Structure will be demolished. The structure is made up of a combination of soil cement and concrete, with rip-rap on each side of the structure. Material disposal will be by pushing the soil cement/concrete and rip-rap debris into the adjacent scour hole located to the south of the structure which is about 90 feet in depth. The removal of the existing Melinda Structure will allow for a uniform rise in water levels in Owens Lake and the Melinda Channel headcut without the risk of damage caused by high head differential flows over the Melinda Structure.
- D. The Historic Cutoff structure will be lowered to a final top of stone elevation of 145. See sheets C-502 and C-504. The proposed alignment is shown on sheet C-102 and its centerline geometry has been included in Attachment A. For purposes of this feasibility study a 1000 foot wide opening is being used with 1:10 side slopes. During the Preconstruction, Engineering & Design (PED) phase of the project, the opening width will be optimized by the Hydrology & Hydraulics section (H&H). The materials excavated from the Historic Cutoff structure will be placed southwesterly

of the proposed opening to create a new backwater embankment that is not directly impacted by the river flows. The excavated area will be protected by a 7 foot layer of R7400 on top of a 1 foot layer of R90 stone and an underlying geotextile. At both the inlet and outlet ends of the channel a 30 foot wide by 20 foot deep stone toe protection trench will be installed and filled with R7400 stone running the full width of the channel and up the 1:10 side slope for 100 feet. Both the R7400 and R90 stone gradations are from the Vicksburg District. The R7400 and R90 gradations are shown in Attachment B. An existing underground powerline and an existing underground fiber optic line are located in the project area and will need to be relocated as part of the New Historic Cutoff construction. Across the excavated area a 24 foot wide by 2 foot thick layer of concrete shall be placed with a top elevation of 145 and maximum 1:10 end slopes as the road transitions to match the existing road. This road will allow for continued access to the Montgomery Point Lock and Dam located 3-miles east of the Historic Cutoff. Underneath the northern half of the road, steel sheet piling shall be installed with a top elevation under the channel of 144 and a bottom elevation of 110 for a length of 2200 feet. Outside of the channel, the top elevation of the sheet piling shall follow the road slope to a final elevation of 170. All disturbed areas will be seeded with a flood resistant, deep rooting seed mixture suitable for growing in sandy conditions. During the Preconstruction, Engineering & Design (PED) phase, a geotechnical study should be performed to determine the best way to control sinkhole issues.

#### **6.1.3 Alternative 2 – Multiple Openings**

There will be three structures constructed as part of the Multiple Openings alternative and two existing structures will be modified. See sheets C-104 and C-105.

A. The Historic Cutoff structure will be lowered to a final top of stone elevation of 135. For purposes of this feasibility study a 2500 foot wide opening is being used with 1:10 side slopes. The materials excavated from the Historic Cutoff structure will be placed southwesterly and southerly of the proposed opening. The final disposal location would need to be determined during the PED phase due to a lack of topographic information to the south of the structure. The excavated area will be protected by a 7 foot layer of R7400 stone on top of a 1 foot layer of R90 stone and an underlying geotextile. At both the inlet and outlet ends of the channel a 30 foot wide by 20 foot deep stone toe protection trench will be installed and filled with R7400 stone running the full width of the

channel and up the 1:10 side slope for 100 feet. Both the R7400 and R90 stone gradations are from the Vicksburg District. The R7400 and R90 gradations are shown in Attachment B. An existing underground powerline and an existing underground fiber optic line are located in the project area and will need to be relocated as part of the New Historic Cutoff construction. Across the excavated area a 24 foot wide by 2 foot thick layer of concrete shall be placed with a top elevation of 145 and maximum 1:10 end slopes as the road transitions to match the existing road. This road will allow for continued access to the Montgomery Point Lock and Dam located 3-miles east of the Historic Cutoff. Underneath the northern half of the road, steel sheet piling shall be installed with a top elevation under the channel of 134 and a bottom elevation of 110 for a length of 2600 feet. All disturbed areas will be seeded with a flood resistant, deep rooting seed mixture suitable for growing in sandy conditions. During the Preliminary, Engineering and Design (PED) phase, a geotechnical study should be performed to determine the best way to control sinkholes issues.

- B. The existing soil cement/concrete Owens Lake Structure is at an elevation of 145. As part of the multiple openings alternative, the structure would be reconstructed by removing a 400 foot section of the soil cement/concrete until the weir is at an elevation of 132. Both ends of the weir would be constructed with a minimum 1:10 slope to allow for vehicular traffic to utilize the structure. For purposes of this report it was assumed that the demolished materials would be repurposed for erosion protection on the Owens Lake side (west side) of the structure.
- C. A new 350 foot long stone structure will be constructed in Owens Lake halfway between the Owens Lake Structure and the Melinda Structure. It shall be constructed entirely of stone with a finished elevation of 135. The basic design shall follow the "New Owens Lake Stone Structure" shown in Details "E" and "F" on sheet C-501, Attachment A. Both ends of the structure shall incorporate 100 foot long stone keyways in each embankment to protect against flanking. A new 1975 foot long by 30 foot wide access road will need to be cleared of trees and stumps to provide access to the site. No aggregate surfacing is proposed at this time.
- D. The existing Melinda Structure is at an elevation of 142 and was constructed originally with soil cement, with repairs being made using concrete. As part of the multiple openings alternative, the structure would be reconstructed by removing a 900 foot section of the soil

cement/concrete until the weir is at an elevation of 132. Both ends of the weir would be constructed with a minimum 1:10 slope to allow for vehicular traffic to utilize the structure. For purposes of this report it was assumed that the demolished materials would be repurposed for erosion protection on the Melinda Headcut channel side (south side) of the structure.

E. A new 600 foot long stone structure will be constructed south of the Melinda Structure near the entrance to the Arkansas River. It shall be constructed entirely of stone with a finished elevation of 129. The basic design shall follow the "New Melinda Stone Structure" shown in Details "E" and "F" on sheet C-501, Attachment A. Both ends of the structure shall incorporate 200 foot long stone keyways in each embankment to protect against flanking. A new 600 foot long by 30 foot wide access road and 100 foot by 110 foot staging area will need to be cleared of trees and stumps to provide access to the site. No aggregate surfacing is proposed at this time.

#### **6.1.4 Environmental Alternatives**

Four environmental alternatives were considered to provide fish passage for La Grues Lake and Owens Lake. Preliminary designs and cost estimates were prepared for them, but were not included in this study. USACE was unable to find a Sponsor for the environmental alternatives, therefore the alternative was dropped from further consideration in the feasibility study.

A. The existing road crossing at the north end of La Grues Lake will have a flow equalization structure consisting of a reinforced concrete arch bridge span with no wing walls similar to Contech's Con/Span O-Series. See the attached Contech sample design in Attachment D. (Note: there are other precast concrete arch bridge manufacturers that can build an arch bridge similar to Contech's. Use of Contech's arch bridge in this study is only for exhibition purposes and does not constitute endorsement.) The inclusion of the arch will allow for flow between the White River and La Grues Lake to allow for the passage of fish between them for longer periods of time. The arch bridge shall have the following nominal dimensions, a rise of 6 feet and a span of 30 feet. The arch will need to be placed upon a concrete footing system set upon piling due to the soft soils anticipated. After installation of the arch, backfilling of the surrounding trench will be done using existing onsite soils and capped by a 12 inch aggregate surface course to restore the road to its existing condition. As part of the construction, the existing buried fiber optic cable will need to be

- relocated. We believe 300 feet of cable will be impacted. Electric power is overhead in this area and should not be impacted.
- B. The existing soil cement/concrete Owens Lake Structure, located at the westerly end of Owens Lake, will be revised to include a flow equalization structure consisting of a reinforced concrete arch bridge span with no wing walls similar to Contech's Con/Span O-Series. See the attached Contech sample design in Attachment D. (Note: there are other precast concrete arch bridge manufacturers that can build an arch bridge similar to Contech's. Use of Contech's arch bridge in this study is only for exhibition purposes and does not constitute endorsement.) The inclusion of the arch will allow for flow between the White River and Owens Lake to allow for the passage of fish between them for longer periods of time. The arch bridge shall have the following nominal dimensions, a rise of 6 feet and a span of 30 feet. The arch will be placed upon the existing soil cement which will act as the footing system. After installation of the arch, backfilling of the surrounding trench will be done with concrete to restore the structural integrity of the Owens Lake Structure. No utilities are expected to be impacted.
- C. The existing soil cement containment structure at the easterly end of Owens Lake will be revised to include a flow equalization structure consisting of a reinforced concrete arch bridge span with no wing walls similar to Contech's Con/Span O-Series. See the attached Contech sample design in Attachment D. (Note: there are other precast concrete arch bridge manufacturers that can build an arch bridge similar to Contech's. Use of Contech's arch bridge in this study is only for exhibition purposes and does not constitute endorsement.) The inclusion of the arch will allow for flow between the White River and Owens Lake to allow for the passage of fish between them for longer periods of time. The arch bridge shall have the following nominal dimensions, a rise of 6 feet and a span of 30 feet and will need to be placed upon a concrete footing system. After installation of the arch, backfilling of the surrounding trench will be done with concrete to restore the structural integrity of the existing soil cement containment structure. As part of the construction, both the existing fiber optic cable and underground powerline will need to be relocated. We believe 300 feet of fiber optic cable and potentially up to 2400 feet of underground power will be impacted.

Running parallel to the soil cement structure is a gravel road used by logging trucks. This gravel road lies within property currently owned by

USACE. Due to elevation differences, the north end of the arch will need to be excavated to allow for water to pass thru easier. This area includes the gravel road which will need to be lowered and restored. Restoration will be by the placement of a 200 foot long, 30 foot wide and 2 foot thick concrete road crossing. In order to control erosion, Class B stone will be placed within the excavated area as needed.

D. The existing La Grues Lake soil cement/rip-rap structure will be demolished in its entirety. The rip-rap that has been placed on-top of the easterly end of the structure, will be removed and stockpiled for future use within the USACE property on the east end of the structure. Where practical, the soil cement shall be broken up and stockpiled adjacent to the rip-rap, otherwise it will be disposed of within the lake and used for bank protection. Where required, sand will be brought in to fill any large voids and to allow for natural revegetation. Disturbed areas will be revegetated upon completion. No utilities are expected to be impacted.

#### 7. STRUCTURAL REQUIREMENTS

The existing Historic Cutoff has been experiencing small sinkholes during high head conditions that could cause a path for subsurface flows to breach the structure. To combat this risk, a steel sheet pile wall system will need to be designed for the No Action Alternative and Alternatives 1 and 2. For the No Action Alternative the top of the sheet pile will be at an elevation of 170 and the bottom at an elevation of 100. The total length of sheet pile to be installed for the No Action Alternative is 5625 feet. For Alternative 1 the top of the sheet pile within the channel will be at an elevation of 144 and the bottom at an elevation of 110. In addition, the top elevation of the sheet pile will follow a 1:10 slope as it gets further from the channel, until it reaches an existing ground level of approximately 170. Total length of sheet pile to be installed for Alternative 1 is 2200 feet. For Alternative 2 the top of the sheet pile within the channel will be at an elevation of 134 and the bottom at an elevation of 110. Total length of sheet pile to be installed for Alternative 2 is 2600 feet. For purposes of this feasibility study, an uncoated 27-inch wide steel sheet pile with a profile section of PZ26 was utilized.

Alternative 1 calls for a bridge supported by a footing system to be installed through the Owens Lake Structure which is made up of a combination of soil cement and concrete in approximately 1 foot layers. In order for this to happen the structural integrity of the existing structure will need to be evaluated. Should the existing structure have sufficient bearing capacity, there is the chance the footing system may not need to be installed and the cost thereto saved.

#### 8. ELECTRICAL AND MECHANICAL REQUIREMENTS

There are no mechanical features in this project.

For both Alternatives 1 and 2, an above ground electrical power line, owned and operated by C&L Electric Cooperative Corporation, has one two-pole system within the Historic Cutoff area to be excavated. These poles will need to be replaced with longer ones to account for the lower ground elevation and to keep the electric connections above the water level. The impacted length of wiring serving the area is approximately 4800 feet long. Design and construction of the electrical modifications would be performed by C&L Electric Cooperative Corporation with USACE reimbursing them for their work.

In addition, USACE owns an underground fiber optic communication cable serving the Montgomery Point Lock & Dam runs thru this same area and must be lowered after the excavation has been completed. Consideration should be given for the installation of the fiber optic cable within a minimum 4 inch PVC conduit installed adjacent to the sheet piling to provide protection from future damage. The anticipated length of fiber optic cable to be relocated is 2500 feet for Alternative 1 and 3000 feet for Alternative 2.

Electrical taking notes and drawings for the fiber optic cable show the general locations installed and are provided in Attachment D.

#### 9. HAZARDOUS AND TOXIC MATERIALS

There will be no hazardous or toxic materials utilized in this project, nor are any expected to be encountered during its construction. A formal Hazardous, Toxic and Radioactive Waste (HTRW) survey is therefore not proposed for this project.

#### 10. CONSTRUCTION PROCEDURES AND WATER CONTROL PLAN

As the Arkansas, White and Mississippi Rivers experience flood events, they will cause the cessation of all construction activities in the Three Rivers Study area. This is especially true for the placement of the geotextile fabric at the Historic Cutoff which cannot be placed underwater. Careful planning and monitoring of river and weather conditions will be required in order for the construction equipment and associated manpower to be evacuated to higher ground prior to a flood event. Due to the volume of water moving through the study area during a flood event, a physical water control plan for the construction site is therefore not feasible. However, localized erosion control measures should be implemented for the construction at the Historic Cutoff.

The construction schedule for the project should take into account mobilization and demobilization of construction equipment and personnel during flood events.

#### 11.INITIAL RESERVOIR FILLING AND SURVEILLANCE PLAN

There are no reservoirs within the project area that would require a Reservoir Filling and Surveillance Plan.

## 12.FLOOD EMERGENCY PLANS FOR AREAS DOWNSTREAM AND UPSTREAM OF CORPS DAMS

There are no dams within the project area that would require a Flood Emergency Plan.

#### 13. ENVIRONMENTAL OBJECTIVE AND REQUIREMENTS

The intent of the study's construction activities is to reduce the flood waters erosive forces which could potentially cause the White and Arkansas Rivers to merge. To accomplish this, Alternative 1 (the TSP) will require the installation of three new structures and the abandonment of one existing structure. Only the new Stone Containment Structure will require additional real estate. This real estate will be limited to the footprint covered by the structure and approximately 20 feet either side for future maintenance access. The other structures will be constructed within property owned by the Government or within the existing river floodways. The preliminary civil design described in Section 6 will become the basis for the final design.

#### 14. RESERVOIR CLEANING

None required.

#### 15. OPERATION AND MAINTENANCE

The project does not require physical operation of any of the features to be implemented. They are totally passive in nature and have no moving parts. As flooding occurs in the Three Rivers area, some stone will be shifted due to the force of the flood waters. In addition, vegetative debris could potentially begin to block the Owens Lake Equalization Structure. The expected maintenance required to maintain these structures would include the replacement of stone in areas where the thickness has been reduced, repair of damaged sections of the existing soil cement structure and the removal of the vegetative debris blocking the Owens Lake Equalization Structure. All these repairs can be accomplished with the use of backhoes to place the stone and trucks to haul it.

#### 16. ACCESS ROADS

Access to Alternative 1's project areas will use the existing roads and structures serving the Three Rivers Study area. The existing roads consist of aggregate stabilized surfaces capable of handling heavy equipment loads. Recently these roads have been used for hauling timber, concrete and stone for structure repairs. Although not recommended for use, the surface of the existing structures consist of soil cement or concrete.

Only Alternative 2 requires additional access roads to be provided. They will be 30 feet wide, located within a 60 foot wide permanent easement and will not have an aggregate surface course. Clearing and grubbing of vegetation will be required in order to utilize

the access roads. It is intended that the construction equipment blade and compact them so they are smooth and stable, in order to allow the off road trucks to deliver the stone for the two structures construction. Upon completion they would be reshaped and seeded.

It should be noted that portions of the existing access road will become inundated when the White River exceeds elevation 140. Also, there are weight restrictions on the existing soil cement structure and the Wild Goose Bayou Bridge. A low water crossing will be required adjacent to the Wild Goose Bayou Bridge for vehicles that exceed the bridge's weight restrictions.

During the Preconstruction, Engineering and Design (PED) phase, the access roads should be re-evaluated to verify that no improvements are required since the preparation of this study. The Contractor will be required to maintain all new and existing access roads used during the projects construction.

Access to the project area will also be available from the White River, especially for the delivery of stone materials.

#### 17. CORROSION MITIGATION

The only metallic item in the project that could be subject to corrosion, is the steel sheet piling. The Historic Cutoff was built with sandy soils obtained from the dredging operations on the White River. These sandy soils allow for better aeration and faster evaporation, but the aeration could also cause the floods wet and dry cycles to increase the rusting/corrosion process on the steel sheet piling. With the presently defined conditions at the site, significant corrosion is not expected to impact the steel sheet piling. However, during Preliminary Engineering Design (PED) phase, a water and soil analysis should be performed to determine the "normal" groundwater level, resistivity and pH at the site. Other material options that could be considered if the water and soil analysis indicates corrosivity to the steel sheet piling, include the use of corrosion resistant piling such as vinyl or Core Ten weathering steel, concrete or slurry cutoff walls, various soil mixing techniques or the use of a cathodic protection system for the steel sheet piling.

#### 18. PROJECT SECURITY

No project security is required, since the location of the construction is very remote and does not involve Government facilities that would require security to be present. During construction, the Contractor will be responsible for the protection of his equipment and personnel.

#### 19. COST ESTIMATES

Cost estimates were prepared for the various alternatives and are included in Appendix F – "Cost Estimate".

#### 20. SCHEDULE FOR DESIGN AND CONSTRUCTION

The schedule for the tentatively selected plan is located within Appendix F – "Cost Estimate".

#### 21. SPECIAL STUDIES

None required.

#### 22. PLATES, FIGURES AND DRAWINGS

Plates, Figures and Drawings have been included in Attachment A of the "Engineering Appendix". They include: plan views of the Stone Containment Structure and the Historic Cutoff channel, typical cross sections of the containment structure, Historic Cutoff and the Owens lake Equalization Structure.

#### 23. DATA MANAGEMENT

During the feasibility study, electronic data was compiled and maintained in project folders for each discipline involved on the server. This data is backed up regularly by USACE's data manager (ACE-IT). The project's information will be available for the next phase of the project.

#### 24. USE OF METRIC SYSTEM MEASUREMENTS

The Sponsor has not specifically requested that the project be designed in English units. However, the river mapping system and property surveys were all done originally in English units. Converting these survey drawings from English to Metric would have created additional work effort and potential translation errors which could affect the design team's efforts resulting in delays to the schedule and additional costs to prepare the study.

# 25. REPORT ON DESIGN AND CONSTRUCTION DEFICIENCIES IN THE DALE BUMPERS WHITE RIVER NATIONAL WILDLIFE REFUGE, ARKANSAS

During the Alternatives Milestone Meeting held on December 15, 2015, the project team was requested to review the report "Correct Design and Construction Deficiencies of Mitigation Structures", dated April 1991 for the Dale Bumpers White River National Wildlife Refuge. On October 11, 2016 a site visit was made to review the problems that said report had identified. The inspection report is located within Attachment C of the "Engineering Appendix". The Army Corps of Engineers completed the required

mitigation structures per the agreement for the construction of the MKARNS channel. The same agreement passed the responsibility for operation and maintenance of the mitigation structures to the US Fish and Wildlife Service (USFWS). At the time of the inspection, no design or construction deficiencies were identified. The issues the USFWS was experiencing at the refuge were the result of facilities meeting their useful life or were impacted by water movement between the green tree reservoirs or flooding from the river. The responsibility for correcting the damages associated with the age of the structure's materials and the river is therefore the responsibility of the USFWS.

### **ATTACHMENT A**

### Plates, Figures and Drawings



## US Army Corps of Engineers®

REVISED FEBRUARY 2018	
EBRUARY 2018	
EBRUARY 2018	
REVISED FI	

XXXXX-XXX/ XXXX

Drawing Ref. No. G-001

# THREE RIVERS STUDY


# MCCLELLAN-KERR ARKANSAS RIVER NAVIGATION SYSTEM (MKARNS)

WHITE RIVER

ARKANSAS COUNTY, ARKANSAS

Solicitation:


Contract:



SHEET INDEX						
DRAWING CODE:	SHEET NO.	TITLE				
	G-001	COVER SHEET				
	G-002	PROJECT LOCATION AND VICINITY MAP-INDEX				
	C-001	PROJECT LOCATION				
	C-101	ALTERNATIVE 1 STONE STRUCTURE				
	C-102	ALTERNATIVE 1 HISTORIC CUTOFF STRUCTURE				
	C-103	ALTERNATIVE 1 OWENS LAKE EQUALIZATION STRUCTURE				
	C-104	ALTERNATIVE 2 HISTORIC CUTOFF STRUCTURE				
	C-105	ALTERNATIVE 2 MULTIPLE OPENING STRUCTURES				
	C-501	DETAILS				
	C-502	ALTERNATIVE 1 HISTORIC CUTOFF PROFILES				
	C-503	ALTERNATIVE 2 HISTORIC CUTOFF PROFILES				
	C-504	ALTERNATIVE 1 HISTORIC CUTOFF SECTIONS				
	C-505	ALTERNATIVE 2 HISTORIC CUTOFF SECTIONS				

NOTE: THESE DRAWINGS ARE LOCATED IN THE FOLLOWING FOLDER LOCATION:

 $\verb|\sw|-netapp2.sw|. ds. usace. army. mil \Shared \ENG Shared \DESIGN \PROJECTS \CIVIL WORKS CORPS \Three Rivers Study \Design Alternatives \InRoads \BOOK \ENGINEERING \BOOK \BOOK$ 





Drawn by: NPG US ARMY CORPS OF ENGINEERS LITTLE ROCK DISTRICT LITTLE ROCK, ARKANSAS


US Army Corps of Engineers® Little Rock District


Drawing Code/ Serial No. XXXXX-XXX/ X80XX


Drawing Ref. No. G-002


























#### **ALTERNATIVE 1 - STONE CONTAINMENT**

#### **STRUCTURE @ ELEVATION 157**

Horizontal Alignment Review Report

Report Created: 1/23/2018 Time: 1:25pm

Project: Model

**Description:** 

\\swl-netapp2.swl.ds.usace.army.mil\Shared\ENG

Shared\DESIGN\PROJECTS\CIVIL WORKS CORPS\Three File Name:

Rivers Study\Design Alternatives\InRoads\InRoads Working

File (2D).dgn

Last 1/23/2018 13:23:42

Revised:

**Note:** All units in this report are in feet unless specified otherwise.

Alignment Name: Unnamed

**Alignment Description: Stone Containment Structure** 

**Alignment Style:** 

	Station	Northing	Easting
Element: Linear			
POB ()	0+00.00	1784992.211	1571669.100
PC ()	10+97.85	1785757.041	1570881.506
Tangential Direction:	N 45°50'24.5" W		
Tangential Length:	1097.85		
Element: Circular			
PC ()	10+97.85	1785757.041	1570881.506
PI ()	12+86.87	1785888.726	1570745.901
CC ()		1786115.740	1571229.837
PT ()	14+59.28	1786077.185	1570731.326
Radius:	500.00		
Delta:	41°25'03.6"	Right	
Degree of Curvature (Arc):	11°27'33.0"		
Length:	361.44		

Tangent:	189.02
Chord:	353.62
Middle Ordinate:	32.31
External:	34.54
Tangent Direction:	N 45°50'24.5" W
Radial Direction:	N 44°09'35.5" E
Chord Direction:	N 25°07'52.7" W
Radial Direction:	N 85°34'39.1" E
Tangent Direction:	N 4°25'20.9" W
Element: Linear	N 7 2020.5 VV
PT ()	14+59.28 1786077.185 1570731.326
PC ()	17+46.17 1786363.220 1570709.204
Tangential Direction:	N 4°25'20.9" W
Tangential Length:	286.89
Element: Circular	200.03
PC ()	17+46.17 1786363.220 1570709.204
PI ()	21+21.80 1786737.731 1570680.239
CC ()	1786247.555 1569213.670
PT ()	24+82.29 1787054.392 1570478.191
Radius:	1500.00
Delta:	28°07'03.9" Left
Degree of Curvature (Arc):	3°49'11.0"
Length:	736.12
•	
Tangent:	375.63
Chord:	728.76
Middle Ordinate:	44.93
External:	46.32
Tangent Direction:	N 4°25'20.9" W
Radial Direction:	N 85°34'39.1" E
Chord Direction:	N 18°28'52.8" W
Radial Direction:	N 57°27'35.2" E
Tangent Direction:	N 32°32'24.8" W
Element: Linear	
PT ()	24+82.29 1787054.392 1570478.191
PC ()	26+62.99 1787206.718 1570380.998
Tangential Direction:	N 32°32'24.8" W
Tangential Length:	180.69
Element: Circular	
PC ()	26+62.99 1787206.718 1570380.998
( )	22

PI () CC ()	27+90.46	1787314.179 1570312.432
CC () PT ()	20.16.56	1786668.827 1569537.984 1787401.002 1570219.100
Radius:	1000.00	1707401.002 1370219.100
Delta:	14°31'43.9"	l oft
Degree of Curvature (Arc):	5°43'46.5"	LGIL
Length:	253.58	
•	127.47	
Tangent: Chord:	252.90	
Middle Ordinate:	8.03	
External:	8.09	
Tangent Direction:	N 32°32'24.8" W	
Radial Direction:	N 57°27'35.2" E	
Chord Direction:	N 39°48'16.8" W	
Radial Direction:	N 42°55'51.3" E	
Tangent Direction:	N 47°04'08.7" W	
Element: Linear		
PT ()	29+16.56	1787401.002 1570219.100
PC ()	30+89.76	1787518.972 1570092.287
Tangential Direction:	N 47°04'08.7" W	
Tangential Length:	173.20	
Element: Circular		
PC ()	30+89.76	1787518.972 1570092.287
PI ()	32+43.68	1787623.810 1569979.590
CC ()		1786786.796 1569411.171
PT ()	33+95.21	1787689.905 1569840.582
Radius:	1000.00	
Delta:	17°30'02.7"	Left
Degree of Curvature (Arc):	5°43'46.5"	
Length:	305.45	
Tangent:	153.92	
Chord:	304.26	
Middle Ordinate:	11.64	
External:	11.78	
Tangent Direction:	N 47°04'08.7" W	
Radial Direction:	N 42°55'51.3" E	
Chord Direction:	N 55°49'10.1" W	
Radial Direction:	N 25°25'48.6" E	
Tangent Direction:	N 64°34'11.4" W	

Element: Linear		
PT (	) 33+95.21 1787689.905 1569	340.582
PC (	) 35+20.36 1787743.648 1569	727.554
Tangential Direction	n: N 64°34'11.4" W	
Tangential Lengt	n: 125.15	
Element: Circular		
PC (	) 35+20.36 1787743.648 1569	727.554
PI (	) 38+42.76 1787882.086 1569	436.399
CC (	1786840.538 1569	298.144
PT (	) 41+44.11 1787824.399 1569	119.209
Radiu	: 1000.00	
Delta	n: 35°44'16.3" Left	
Degree of Curvature (Arc	): 5°43'46.5"	
Lengt	e: 623.74	
Tanger	t: 322.39	
Chor		
Middle Ordinate	e: 48.24	
Externa	l: 50.68	
Tangent Direction	ı: N 64°34'11.4" W	
Radial Direction	n: N 25°25'48.6" E	
Chord Direction	: N 82°26'19.6" W	
Radial Direction	: N 10°18'27.7" W	
Tangent Direction	s 79°41'32.3" W	
Element: Linear		
PT (	) 41+44.11 1787824.399 1569	119.209
PC (	) 46+65.85 1787731.041 1568	305.885
Tangential Direction	s: S 79°41'32.3" W	
Tangential Lengt	n: 521.74	
Element: Circular		
PC (	) 46+65.85 1787731.041 1568	305.885
PI (	) 49+12.73 1787686.865 1568	362.986
CC (	) 1786255.250 1568	374.287
PT (	) 51+55.23 1787567.172 1568	147.059
Radiu	: 1500.00	
Delta	ı: 18°41'34.5" Left	
Degree of Curvature (Arc	): 3°49'11.0"	
Lengt	: 489.38	
Tanger	t: 246.88	
Chor		

Middle	Ordinate:	19.91	
	External:	20.18	
Tangent	Direction:	S 79°41'32.3" W	
Radial	Direction:	N 10°18'27.7" W	
Chord	Direction:	S 70°20'45.1" W	
Radial	Direction:	N 29°00'02.2" W	
Tangent	Direction:	S 60°59'57.8" W	
Element: Linear			
PT	()	51+55.23	1787567.172 1568147.059
PC	()	62+41.12	1787040.711 1567197.323
Tangential	Direction:	S 60°59'57.8" W	
Tangenti	al Length:	1085.89	
Element: Circular			
PC	()	62+41.12	1787040.711 1567197.323
PI	()	68+39.33	1786750.686 1566674.116
CC	()		1785291.482 1568166.960
PT	()	74+03.67	1786221.006 1566396.089
	Radius:	2000.00	
	Delta:	33°18'16.5"	Left
Degree of Curva	ture (Arc):	2°51'53.2"	
	Length:	1162.55	
	Tangent:	598.21	
	Chord:	1146.25	
Middle	Ordinate:	83.88	
	External:	87.55	
Tangent	Direction:	S 60°59'57.8" W	
Radial	Direction:	N 29°00'02.2" W	
Chord	Direction:	S 44°20'49.6" W	
Radial	Direction:	N 62°18'18.7" W	
Tangent	Direction:	S 27°41'41.3" W	
Element: Linear			
PT	()	74+03.67	1786221.006 1566396.089
PC	()	83+88.84	1785348.698 1565938.218
Tangential	Direction:	S 27°41'41.3" W	
Tangenti	al Length:	985.17	
Element: Circular			
PC	()	83+88.84	1785348.698 1565938.218
PI	()	89+93.33	1784813.460 1565657.273
CC	()		1785813.460 1565052.782

PT () 94+76.27 1784813.460 1565052.782

Radius: 1000.00

Delta: 62°18'18.7" Right

Degree of Curvature (Arc): 5°43'46.5"

Length: 1087.43

Tangent: 604.49 Chord: 1034.64

Middle Ordinate: 144.21

External: 168.51

Tangent Direction: S 27°41'41.3" W
Radial Direction: N 62°18'18.7" W
Chord Direction: S 58°50'50.7" W
Radial Direction: N 0°00'00.0" E

Tangent Direction: N 90°00'00.0" W

Element: Linear

PT () 94+76.27 1784813.460 1565052.782 POE () 121+00.00 1784813.460 1562429.056

Tangential Direction: N 90°00'00.0" W Tangential Length: 2623.73

# **ALTERNATIVE 1 - HISTORIC CUTOFF STRUCTURE**

# Horizontal Alignment Review Report

Report Created: 12/7/2017 Time: 11:37am

Project: Model

**Description:** 

\\swl-netapp2.swl.ds.usace.army.mil\Shared\ENG

Shared\DESIGN\PROJECTS\CIVIL WORKS CORPS\Three

Rivers Study\Design Alternatives\InRoads\InRoads Working

File (2D).dgn

**Last Revised:** 12/7/2017 11:18:34

**Note:** All units in this report are in feet unless specified otherwise.

Alignment Name: GeomCL

Alignment Description: Historic Cutoff – Alternative 1

Alignment Style: Geom\_Centerline

		Station	Northing	Easting
Element: Circular	_			
PC	()	0+00.00	1781178.295	1573169.792
PI	()	9+58.88	1782136.995	1573151.125
CC	()		1781225.015	1575569.337
PT	()	18+24.50	1782844.620	1573798.213
	Radius:	2400.00		
	Delta:	43°33'24.5"	Right	
Degree of Curvatu	ure (Arc):	2°23'14.4"		
	Length:	1824.50		
	Tangent:	958.88		
	Chord:	1780.89		
Middle (	Ordinate:	171.30		
	External:	184.46		
Tangent [	Direction:	N 1°06'55.5" W		
Radial [	Direction:	N 88°53'04.5" E		
Chord [	Direction:	N 20°39'46.7" E		
Radial [	Direction:	S 47°33'31.1" E		
Tangent [	Direction:	N 42°26'28.9" E		

# **ALTERNATIVE 1 - HISTORIC CUTOFF STRUCTURE**

# Vertical Alignment Review Report

Report Created: 12/7/2017 Time: 11:42am

Project: Model

**Description:** 

\\swl-netapp2.swl.ds.usace.army.mil\Shared\ENG

Shared\DESIGN\PROJECTS\CIVIL WORKS CORPS\Three File Name:

Rivers Study\Design Alternatives\InRoads\InRoads Working

File (2D).dgn

Last 12/7/2017 11:39:04 Revised:

**Note:** All units in this report are in feet unless specified otherwise.

Horizontal Alignment: GeomCL

Horizontal Description: Historic Cutoff -Alternative 1

Horizontal Style: Geom\_Centerline

Vertical Alignment: Unnamed

**Vertical Description: Vertical Style:** 

	Station	Elevation
Element: Linear		
POB	3+00.00	130.0
PVI	8+00.00	145.0
Tangent Grade:	3.00%	
Tangent Length:	500.00	
Element: Linear		
PVI	8+00.00	145.0
PVI	11+00.00	145.0
Tangent Grade:	0.00%	
Tangent Length:	300.00	
Element: Linear		
PVI	11+00.00	145.0
POE	15+50.00	137.0
Tangent Grade:	-1.78%	
Tangent Length:	450.00	

## **ALTERNATIVE 2 - HISTORIC CUTOFF STRUCTURE**

# Horizontal Alignment Review Report

Report Created: 1/19/2018 Time: 12:31pm

Project: Model

**Description:** 

\\swl-netapp2.swl.ds.usace.army.mil\Shared\ENG

Shared\DESIGN\PROJECTS\CIVIL WORKS CORPS\Three

File Name: Rivers Study\Design Alternatives\InRoads\InRoads Working

File (2D).dgn

**Last** 1/19/2018 12:28:38 Revised:

**Note:** All units in this report are in feet unless specified otherwise.

Alignment Name: Historic Cutoff – Alternative 2

Alignment Description: Channel Centerline

**Alignment Style:** 

Station Northing **Easting** Element: Linear POB 0+00.00 1781727.733 1572440.033 ()

POE () 20+00.00 1782942.066 1574029.182

Tangential Direction: N 52°36'54.4" E

Tangential Length: 2000.00

# **ALTERNATIVE 2 - HISTORIC CUTOFF STRUCTURE**

Vertical Alignment Review Report

Report Created: 1/19/2018

Project: Model

Description:
File Name:
Last Revised:

**Note:** All units in this report are in feet unless specified otherwise.

Horizontal Alignment: Unnamed

Horizontal Description: Historic Cutoff – Alternative 2

**Horizontal Style:** 

Tangent Length:

Vertical Alignment: Unnamed

**Vertical Description:** Historic Cutoff – Alternative 2

Vertical Style: Channel Centerline

	Station	Elevation
Element: Linear		
POB	Varies	Varies
PVI	Varies	135.0
Tangent Grade:	3.30% Max	
Tangent Length:	Varies	
Element: Linear		
PVI	Varies	135.0
PVI	Varies	135.0
Tangent Grade:	0.00%	
Tangent Length:	Varies	
Element: Linear		
PVI	Varies	135.0
POE	Varies	Varies
Tangent Grade:	-3.30% Max	

The stationing for all POB's, PVI's and POE's varies. It is the intent for the PVI to be at elevation 135 and match the existing contour location. The POB's and POE's shall be at the approximate toe of the existing slopes. Tangent Lengths and Tangent Grades (except between PVI's) will vary as a result.

Varies

## THREE RIVERS STUDY

# PRECONSTRUCTION, ENGINEERING & DESIGN (PED)

## March 2018

## The following tasks should be looked at further during the PED phase.

- 1. Prepare Hydrographic and Topographic survey for the project areas. Insufficient hydrographic and topographic information was available when the feasibility study was prepared.
- 2. Obtain soil borings for the Historic Cutoff Structure.
  - a. The subsurface investigation program should be sufficiently robust to adequately characterize the foundation under this structure in order to design and optimize the sheet piling and under seepage controls.
  - b. Determine the failure mechanism for the sinkholes currently being experienced.
  - c. In lieu of steel sheet piling, determine alternative methods for correcting the sinkhole issue. (Note: the feasibility report used a conservative and costly approach that sheet piling was required. Hopefully further study during PED can result in the elimination of the sheet piling from the project.)
  - d. A water and soil analysis should be performed to determine the "normal" groundwater level, resistivity and pH at the site. (IE: corrosivity study to determine if steel sheet piling can be used.)
- Determine the appropriate means to combat corrosion of the "steel sheet pile wall system". This could include material changes or different construction techniques. See the feasibility study's Engineering Appendix C, Paragraph 17 for further discussion.

#### Owens Lake Structure:

- a. Provide design for anchoring the new concrete to the existing soil cement structure and the new concrete bridge deck to the precast concrete bridge unit. (IE: keyways, rebar anchors and bonding agents, etc.) Of major design concern is the new concrete bridge deck delaminating from the precast concrete bridge during a flood event. (Note: this type of failure previously occurred with the soil cement at the existing Melinda Structure.)
- b. Design consideration should also be made for preventing water movement between the contact surfaces such as the existing soil cement and new concrete and the new concrete and the precast concrete bridge. (IE: examples would be to use keyways and Hydrophilic (swelling) waterstops, etc.)

- 5. The Owens Lake Structure currently has an invert elevation of 140. Discuss with H&H, Environmental and the USFWS the benefits of lowering the invert to elevation 135. This would keep the top elevation of the Owens Lake Structure at the same level as currently exists.
  - a. Elevation 140 is the current elevation in which water exchanges with the Arkansas River, but due to leakage through both the Melinda and Owen's Lake structures, the water surface elevation in Owen's Lake may closely mimic the water surface elevation in either the Arkansas or White Rivers. H&H expects the new containment structure at elevation 157 to "leak" like the existing Melinda structure since its design consists of rock without a clay or impermeable core.

Placing 3 staff gages around Owens Lake will help determine the final design elevation of the Owens structure for PED. One in Owens lake, one in the White River immediately north of the Owens Lake Structure and one in the Arkansas River immediately south of the Melinda Structure.

The water surface elevation data from the three staff gages can be supplied to fishery biologists to maximize spawning, fish passage, and other habitat benefits. It is believed that this will be a minimal level of effort once water surface elevation data is acquired. But currently, this data does not exist.

- b. The questions to be addressed are as follows:
  - Does the invert elevation of the structure change the hydrology of the area significantly? (IE: is the area wetter or drier)
  - ii. Does the lower invert elevation offset any changes in hydrology by allowing greater fish movement through the structure?
  - iii. How does the hydrology affect the bottomland hardwood trees?
- c. If the invert can be lowered to elevation 135, consider changing the structure type back to a 65 foot long, 6'x30' reinforced concrete arch bridge, with no wing walls similar to Contech's Con/Span O-Series. See the attached Contech sample design in Attachment D.
- 6. Determine if 20 foot temporary easements are required on both sides of the Stone Containment Structure or can construction occur within the proposed right of way? The question to be answered is how much room is required for the placement of the stone and the excavated material on the slopes?
- 7. The excavated material under the Stone Containment Structure could be used as topsoil at the Historic Cutoff. Using the excavated material as topsoil will affect the answer for question 6 above.

- 8. Can the demolished material from the Melinda Structure be used for the core of the Stone Containment Structure as it crosses the Melinda Headcut? This could result in a possible cost savings because the stone materials for the crossing would not need to be acquired, nor additional easements.
- The channel area south of the Historic Cutoff Structure should be looked at further. Does it require additional armoring of the embankments to prevent erosion or should additional real estate be purchased to prevent the possibility of damage claims. This discussion needs to be coordinated with Real Estate and H&H.
- 10. A careful evaluation of construction phasing for the Historic Cutoff Structure must be considered to prevent failure during a flood event. Do not excavate everything to final grade at one time! (Example Phasing: 1. Excavate and armour the slopes entering and exciting the structure. Decide how much length must be done before moving to step 2? 2. Excavate the plateau area to elevation 137 for a reasonable length that can be armoured before a flood event. 3. Install sheet piling. 4. Install stone to final grade. Progressively move across the width of the channel.)
- 11. Work with the Cost Engineers to look at the long term OMRRR costs of the projects structures in order to get a better cost estimate.
- 12. In order to protect the fiber optic cable to Montgomery Point L&D and insure its continued operation in a flood event, H&H wants to replace the existing damaged culverts at the north end of Lagrues Lake as they enter the White River. Utilize a 60-inch diameter polypropolene pipe (manufacturer ADS) at the location approximately 750 feet north of the abandoned railroad bridge. This type and size of pipe has been utilized by the USFWS at other locations along this road. Coordinate the invert elevation with the USFWS. They may want the pipe invert as low as possible to allow for fish passage over a longer time period.
- 13. For the Historic Cutoff Structure, H&H is coordinating with USACE's Engineer Research and Development Center (ERDC) to have a Ship Tow Simulation performed prior to commencement of the PED phase of the project. The simulation will be used to insure that there are no dangerous cross currents from the White River into the Historic Cutoff Channel and to optimize the width of the Historic Cutoff Structure, which is currently set at 1000 feet.
- 14. For the Stone Containment Structure as it crosses the Melinda Headcut Channel, verify that the preliminary keyway design shown on plan Sheet C-501, Detail F is required. If required, verify that the keyway size and length is correct. After the Geotechnical analysis is completed, determine if a granular or geotextile filter is required to prevent the migration of fine granular materials thru the keyway and under the Stone Containment Structure for its full length.

# **ATTACHMENT B**

Rock Gradation for the Proposed Weir through the Historic Cutoff Containment Structure

# Three Rivers:

# Rock Gradation for the Proposed Weir through the Historic Cutoff Structure Table of Contents

Table of	f Contents
1 Roc	ck Gradation for the Proposed Weir through the Historic Cutoff Structure2
1.1	Summary2
1.2	Maximum Discharges
1.3	D <sub>50</sub> Calculations
1.4	Gradation Curve
1.5	Plotting on Gradation curve5
Table of	Figures
Figure 1	: Equivalent Weight: EM 1110-2-1601: 1994
Figure 2	2: Gradation D50=30 inches
Figure 3	S: Gradation D50=33 inches6

## 1 Rock Gradation for the Proposed Weir through the Historic Cutoff Structure

## 1.1 Summary

Final rock size falls in the USACE standard R7400 gradation.

## 1.2 Maximum Discharges

Calibrated HEC RAS output hydrographs from the Spring 2011 flood event was used to develop maximum discharges for the 500 foot and 1,000 foot proposed openings in the Historic Cutoff Structure.

Maximum Discharge for 500 foot opening: 82,000 cfs Maximum Discharge for 1000 foot opening: 120,000 cfs

## 1.3 D<sub>50</sub> Calculations

Seven methods or equations were used to calculate the  $D_{50}$  based on depth average flow velocity, depth of flow, unit discharge, bed slope, and other equation specific factors for rock shape, turbulence, etc as required for each equation. The seven results were averaged to come up with a D50 of 31.7 inches for the 500 foot opening with a 1V:20H bed slope and a factor of safety of 1.2.

Table 1: D<sub>50</sub> for 7 methods, 500 foot opening

500 Foot Opening				
Method	1V:10H D50 (inches)	1V:20H D50 (inches)	Factor of Safety	
Rock Spillway 2	56.9	41.1	1.2	
Rock Spillway 3	37.0	29.7	1.2	
NRCS Rock chute	48.4	27.9	1.2	
ARS Rock chute	48.6	27.9	1.2	
Method 1	29.3	29.3	1.2	
Abt and Johnson	40.4	30.0	1.2	
US Burea of Rec	36.1	36.1	1.2	
Average:	42.4	31.7	1.2	

Next, an excel program based on Design of Rock Chutes was used calculate the  $D_{50}$  for both the 500 foot and 1000 foot opening. The program took into consideration the hydraulic parameters mentioned in the previous 7 equations and the physical orientation and geometry of the weir such as the upstream and downstream channel slopes, width, Manning's n-values, and headwater and tailwater elevations.

The 500 foot opening resulted in a larger D50 than the 1000 foot opening and so was used to determine the rock gradation for the weir through the Historic Cutoff Structure. Rock sizes of 30 inches and 33 inches were both used to develop gradation curves.

Table 2: D50 Based on Design of Rock Chutes

(Version WI-July-2010, Based on Design of Rock Chutes by Robinson, Rice, Kadavy, ASAE, 1998

	1V:10H	1V:15H	1V:20H	
Opening Size	D <sub>50</sub> (inches)	D <sub>50</sub> (inches)	D <sub>50</sub> (inches)	Factor of Safety
500	46.4	33.5	26.7	1.2
1000	40.5	29.3	23.3	1.2

#### 1.4 Gradation Curve

The  $D_{50}$  was then used to calculate the average  $D_{100}$ ,  $D_{80}$ ,  $D_{50}$ , and  $D_{10}$  using the table below.

Bank Protection 15 - 19

weigh 3000 pounds. Table 15-4 can be used to develop the gradation limits of any riprap class. D<sub>50</sub> and W<sub>50</sub> are the equivalent spherical diameter and weight of the median stone size.

Table 15-4: Riprap Gradation Limits

Stone Size (feet)	Stone Weight (Ibs)	Percent of Gradation Smaller Than
1.44D <sub>50</sub> to 1.71D <sub>50</sub>	3W <sub>50</sub> to 5W <sub>50</sub>	100
1.26D <sub>50</sub> to 1.40D <sub>50</sub>	2W50 to 2.75W50	80
1.00D <sub>50</sub> to 1.14D <sub>50</sub>	W <sub>50</sub> to 1.5 W <sub>50</sub>	50
0.46D <sub>50</sub> to 0.58D <sub>50</sub>	0.1W <sub>50</sub> to 0.2W <sub>50</sub>	10

Equivalent weights were calculated using two methods with a specific gravity of 2.6. The first method was to take the average volume of a sphere and a cube the second method was taken out of EM 110-2-1601. See Figure 1: Equivalent Weight: EM 1110-2-1601: 1994




Figure 1: Equivalent Weight: EM 1110-2-1601: 1994

Gradation curves were developed for both the  $D_{50} = 30$  inches and  $D_{50} = 33$  inches. See Table 3 and Table 4

Table 3: Gradation  $D_{50} = 30$  inches

D <sub>50</sub> =	30.00 inches		
Average '	Weight (lbs): Speci	ific Gravity 2.6	
Stone Size	Weight Between sphere and cube	Weight: EM 1110-2-1601	
D100	7710	5297	
D80	4580	3147	
D50	2396	1646	
D10	282	194	

Table 4: Gradation  $D_{50} = 33$  inches

D <sub>50</sub> =	33.00	inches
Average Weight (lbs): Specific Gravity 2.6		
Stone Size	Weight Between sphere and cube	Weight: EM 1110-2-1601
D100	10262	7051
D80	6096	4189
D50	3189	2191
D10	376	258

# 1.5 Plotting on Gradation curve

Both gradations were plotted against the standard R7400 gradation. See Figure 2 and Figure 3 for plotting results.




Figure 2: Gradation D<sub>50</sub>=30 inches








Figure 3: Gradation  $D_{50}$ =33 inches









# ATTACHMENT C

Report on Design and Construction Deficiencies in the Dale Bumpers White River National Wildlife Refuge, Arkansas



#### **DEPARTMENT OF THE ARMY** LITTLE ROCK DISTRICT, CORPS OF ENGINEERS P.O. BOX 867 LITTLE ROCK, ARKANSAS 72203-0867

www.swl.usace.army.mil

CESWL-EC-DG October 11, 2016

#### MEMORANDUM FOR RECORD

SUBJECT: Site Visit to Inspect MKARNS Construction Deficiencies of Mitigation Structures Dale Bumpers White River National Wildlife Refuge (WRNWR), Arkansas

On this date a site visit was made to the WRNWR, specifically that area located north of the MKARNS channel and west of the White River. Present during the site visit were the USACE employees Norman Gartner, David "Craig" Hillburn and Cherrie-Lee Phillp and US Fish and Wildlife Service (USFWS) employees Charles "Bo" Sloan, Arthur "Jay" Hitchcock, and Jason Phillips. The Letter Report entitled "Correct Design and Construction" Deficiencies of Mitigation Structures" dated April 1991 identified the mitigation structures that were to be corrected. This report is included for reference at the rear of this memorandum. It should be noted that since the 1991 report was completed, USACE has not performed any corrective action to these structures. During the December 15, 2015, Alternatives Milestone Meeting (AMM), USACE Headquarters requested that this report be revisited and the mitigation structures be re-inspected to see if additional damage has occurred. Below are the results of the site visit to the damaged mitigation structures and to other areas within the WRNWR that the USFWS requested to be looked at. Specific locations area identified on the attached Location Map.

## Mitigation Deficiencies from 1991 Report

## Area 1

## A. Twin 60 inch Sluice Gate Control Structure.

The north slide gate has been replaced by Ducks Unlimited under contract with the USFWS. A "Hydrogate", Model IB5, with a 4:1 lift ratio was used to replace the original sluice gate. See Figure 1.

The south slide gate is still the original one installed. It has been partially disassembled and is currently inoperable. See Figures 2 and 3. In addition, the gate's guide brackets are not anchored to the concrete wall due to corrosion of the existing anchor bolts. See Figure 4. An attempt to re-anchor the guide brackets was never completed.

For the south slide gate, the concrete is pitted and at some locations adjacent to the stop log channels has broken away. In addition, the steel guide channels for the stop logs has corroded and is partially missing. See Figure 5. Vegetative and earthen debris has partially blocked the use of the gates. See Figures 5 and 6.

The settlement and resulting cracking identified in the above referenced report was not immediately visible during this inspection.

Recommendation: The south slide gate should be repaired or replaced to restore its operability. Where missing, the steel guide channel and concrete should be repaired. Both slide gates should be re-anchored to the concrete wall. All vegetative and earthen debris should be removed to insure successful operation of the entire structure as designed.

## B. 36 inch CMP Culvert

The 36 inch CMP culvert located north of the sluice gate was replaced by Ducks Unlimited in 2003 under contract with the USFWS. The pipe is now a 5 foot diameter steel pipe with a sluice gate.

Recommendation: No further action is required.

# C. <u>36 inch CMP Culvert</u> (Not part of original deficiencies.)

The 36 inch CMP culvert located 4780 feet east of the sluice gate has been lined with a ½ inch polyethylene liner that was pulled thru the pipe with no other work being performed on the pipe. The installation of the liner was done by slicing slits in the end to facilitate pulling it thru the CMP. The liner was not pulled all the way thru the pipe so the slits still remain inside the pipe. The ends of the pipe seem to have a direct connection to the ground surface because some settlement has occurred on the surface, possibly due to soil migration into the pipe. The upstream end also has sediment deposition which should be removed. Who installed the liner is unknown.

Recommendation: With the exception of the end areas, the liner does seem to be functioning, however USACE's preferred method of repair would have been to use the SnapTite liner system and grout the annular space that remains to restore the pipes structural integrity and prevent soil intrusion. The USFWS should periodically inspect the liner to insure further failure has not occurred. Other than removal of the sediment deposit at the upstream end of the pipe, no further action is recommended.

## D. <u>36 inch CMP Culvert</u> (Not part of original deficiencies.)

The 36 inch CMP culvert located 5440 feet east of the sluice gate has been lined with a ½ inch polyethylene liner that was pulled thru the pipe with no other work being performed on the pipe. The installation of the liner was done by slicing slits in the end to facilitate pulling it thru the CMP. The liner was not pulled all the way thru the pipe and remains inside the pipe. The liners ends also have poor adhesion at the top. See Figure 7. The upstream end of the pipe seems to have a direct connection to the ground level because some settlement has occurred on the surface, possibly due to soil migration into the pipe. The upstream end also has sediment deposition which should be removed. See Figure 8. Who installed the liner is unknown.

Recommendation: With the exception of the end areas, the liner does seem to be functioning, however USACE's preferred method of repair would have been to use the SnapTite liner system and grout the annular space that remains to restore the pipes structural integrity and prevent soil intrusion. The USFWS should periodically inspect the liner to insure further failure has not occurred. Other than removal of the sediment deposit at the upstream end of the pipe, no further action is recommended.

## Area 2

This area was not inspected because the Deficiencies Report identified that there was "No economical justifiable repair to recommend".

# Area 3

The 36" CMP was not visible during this site visit. It can only be assumed that it has been filled in or removed as previously recommended in the Deficiencies Report. The levee in this area was also in good structural shape.

Recommendation: No further action is required.

## Area 4

As mentioned in the Deficiencies Report the culvert has been replaced by the USFWS with a 36" CMP. The outlet looked like it had been armored with a combination of stone and concrete. See Figure 9. The existing levee looked in good shape and did not appear to require widening or additional stone protection. The drainage from the culvert does not go directly to the river but turns southerly and follows an old channel between the levee and the river. This channel has experienced some erosion in localized areas that are not very big. The USFWS has indicated that the sluice gate and culvert are not currently being used and that their preference would be to block them. These issues appear to fall within the Operation and Maintenance obligations of the USFWS.

Recommendation: No further action is required.

# New Erosion Area (Not part of original deficiencies.)

Approximately 6250 feet north of Area 4, the White River's embankment is within 50 feet of Levee A. At the time of the inspection, it was impossible to tell how active the river erosion process is in the area. Aerial photos reviewed back to 1994 on Google Earth did not show a very active erosion process. It is therefore impossible to determine if the levee is in imminent risk or whether the river will move away from this area.

Recommendation: Perform annual inspections of this area to determine if the river is continuing to erode the embankment. To do this establish fixed points to measure from towards the river and create a database to determine how fast the erosion is occurring. If erosion is determined to be a problem, approximately 3000 feet of stone bank protection

may be required to protect the embankment area. The final design of any stone bank protection required would be determined in the future.

## Area 5

The White River has destroyed approximately 1300 feet of Levee "A" used as mitigation for the MKARNS project. The USFWS has built a new levee west of the White River. Starting approximately 8200 feet east of Area 1 and extending north until it intersects with Levee "A". Constructing this new levee was the recommendation in the Deficiencies Report. This new levee has removed approximately 175 acres of land from the "green tree reservoir" that the levee was to create for mitigation. Since this new levee has been constructed, the need for restoring the destroyed portion of Levee "A" is uncertain. In addition, a 60 inch CMP culvert located 8150 feet east of Area 1's sluice gate, has been constructed by Ducks Unlimited under contract with the USFWS.

Recommendation: No further action is required.

## Dry Lake Structure (Not part of original deficiencies.)

During the site visit the USFWS requested that the Dry Lake Gate Structure be looked at. Figures 10 – 16 provide representative views of the structure. A visual inspection indicated the structure was in good shape. Some minor repairs are required. They include rehabilitating and adding a protective coating to the trash racks to repair the holes which have appeared over time. The second would be to replace the missing covers over the grating. See Figure 14. The structures outlet pipe is served by two CMP of unknown size. No physical damage was witnessed, but due to their age it is believed they are approaching their useful life and should be considered for lining sometime in the near future.

## Conclusion

Per the 1964 permit, a copy of which is included in the attached deficiency report, USACE was to design and construct the mitigation structures while the USFWS was to operate and maintain them. At the time of the inspection, no design or construction deficiencies were identified. In addition, the problems being experienced by the USFWS appear to be normal maintenance issues. Many of the issues the USFWS is experiencing are the result of facilities meeting their useful life or were physically impacted by water movement between the green tree reservoirs or flooding from the river. The responsibility for correcting the damages associated with the age of the structure's materials and the river is therefore the responsibility of the USFWS.

There were 41 photos taken of the different areas and placed in the following folder: "L:\ENG Shared\DESIGN\PROJECTS\CIVIL WORKS CORPS\Three Rivers Study\Photos\MKARNS Deficiencies". Representative photos of various items found have been attached as figures at the rear of this report.

Norman Gartner, P.E. USACE General Engineering Section CESWL-EC-DG



Figure 1 - Area 1, New Gate Mechanism installed by USFWS in 2003.



Figure 2 - Area 1, Existing Gate Mechanism (Note that it has been disassembled.)





Figure 4 - Area 1 - Existing southern slide gate. Note that the anchor bolts are not connected.



Figure 5 - Area 1, Debris and missing guide frame and concrete spalling. North side of the southern 60" concrete pipes inlet.



Figure 6 - Area 1, Debris and guide frame. South side of the southern 60" concrete pipes inlet.



Figure 7 - Existing 36" CMP, 5440 feet east of Area 1. Typical liner installation. Note the poor liner adhesion at the pipes entrance.



Figure 8 - Existing 36" CMP inlet 5440 feet east of Area 1. Typical guide installation. Note sediment on upstream side.





Figure 10 - Dry Lake Structure. (Not part of original mitigation deficiencies.)






Figure 12 - Dry Lake Structure. (Not part of original mitigation deficiencies.)



Figure 13 - Dry Lake Structure. (Not part of original mitigation deficiencies.)








Figure 16 - Dry Lake Structure Outlet. (Not part of original mitigation deficiencies.)





## WHITE RIVER NATIONAL WILDLIFE REFUGE, ARKANSAS

# CORRECT DESIGN AND CONSTRUCTION DEFICIENCIES OF MITIGATION STRUCTURES



LETTER REPORT APRIL 1991

#### TABLE OF CONTENTS

Background	1
Description of Original Project	1
Description and History of Deficiencies	1
History of Repairs by Local Interests	2
History of Project Alterations by Local Interests Since Project Completion	3
Proposed Corrective Measures	3
Alternative Corrective Measures Considered	4
Estimated Cost of Corrective Measures	4
Justification	4
Cost Sharing	6
Environmental Considerations	6
Recommendations	8

#### LIST OF PLATES

- Project Location
   Project Summary
   Details 1

- 4. Details 2

#### LIST OF APPENDICES

- A. U.S. Fish & Wildlife Permit (Part)B. List of Project DeficienciesC. Cost Estimate Summary

## Letter Report Rehabilitation of Deteriorating Structures White River National Wildlife Refuge

- 1. <u>Background</u>. Construction of the Arkansas Post Canal as a part of the McClellan-Kerr Arkansas River Navigation System was started during the early 1960's. A portion of the canal was constructed through the White River National Wildlife Refuge, which is managed by the U.S. Fish and Wildlife Service (hereinafter referred to as "the Service"). Under the terms of a permit with the Service dated 2 January 1964 (Appendix A), the Corps was required to construct a containment levee system with gate structures (Plates 1-4) as mitigation measures.
- 2. Description of Original Project. The project consists of a system of levees that form three shallow greentree reservoirs with nine drainage structures providing water management. The purpose of the project was to develop and manage waterfowl resources on approximately 2,540 acres of refuge lands located north of the Arkansas Post Canal. The project was provided as mitigation for the loss of canal right-of-way (534 acres) and the "loss" of 568 acres of refuge land that was isolated south of the canal.
- 3. <u>Description and History of Deficiencies</u>. Areas 1-5 in this report correspond with those in previous correspondence and memorandums for record and are shown on Plate 2. Appendix B provides a detailed chronological listing of project problems and deficiencies.
- A. Structural Deficiencies. Design and construction deficiencies in Area 1 were cited in a 1989 district memorandum as reasons for the following problems:
- (1) Settlement of the 60" twin sluice gate structure in Levee B has caused cracking of the headwall. Poor concrete contributed to spalling at the gate support bracket. These problems caused the binding of one gate and breaking of its gate support bracket anchor bolt in 1984.
- (2) The 36" slide gate located about 100 feet north of the twin 60" structure has failed. The gate reportedly "popped off" and has been missing since 1978.
- B. Hydraulic Deficiencies. Levee A has been partially destroyed by the action of White River headcutting in Areas 3, 4, and 5 reportedly due to channelization of the White River below the Arkansas Post Canal. In 1967 the Service requested that the Corps take immediate measures to provide bank stabilization for those portions of the River subject to greatly increased erosion. This was not done.

- (1) Area 2: Although this area has experienced significant erosion by the White River, the Service has indicated that it would not be feasible to perform all repairs that would be required.
- (2) Area 3: A portion of the original section of Levee A in Area 3 and the 36" gate structure were lost due to the action of bank caving and was later rebuilt by the Service some distance inland from the White River. The new levee and gate structure became damaged by the action of floodwaters overtopping the sheet pile headwalls and eroding behind the sheet piles. This erosion was subsequently arrested by the installation of sheet pile wingwalls and stone slope protection. Although the gate structure was saved, the levee crown had eroded from 10 feet to approximately 5 feet in width, preventing occasional vehicle travel along the levee by the Service for inspections. Service has requested that a 100-foot section of levee in this area be reconstructed to the full 10-foot crown width and that slope protection be provided to extend longevity. Additionally, the Service no longer has a need to operate the 36" gate structure, and requests that it be removed from the levee or that the 36" corrugated metal pipe (cmp) be plugged with concrete.
- (3) Area 4: The Service installed two concrete spillways in 1981 and placed rip rap along the levee for erosion protection. The Service also replaced a deteriorated 36" cmp gate structure with an 18" concrete pipe. The Service requests that stone protection be placed on the slopes around each end of the 18" pipe to prevent additional erosion.
- (4) Area 5: The Service has estimated the loss of approximately 900 feet of Levee A due to the action of the White River. This has eliminated the Levee A road connecting with Wild Goose Landing. To keep from losing all of the use of Reservoir A, the Service installed a new section of levee with gate structure in a slough inland from the White River. The Service requests that the levee be rebuilt farther inland, perhaps utilizing this Service section of levee. The estimated length is 1,500 lineal feet.
- 4. <u>History of Repairs by Local Interests</u>. It appears that the Service has adequately attempted to maintain the subject structures since they were constructed.
- A. Service memo, 27 April 1987, stated that "In the ensuing 20 years since construction, the Service has performed operation and maintenance (O&M) for all the completed mitigation features. The O&M activities to date have consisted primarily of adding gravel to the levees, minor repair of the levees or access roads, and other similar actions. ".... the costs of these activities .... represent a sizeable portion of the annual budget of White River NWR."

- B. On 8 February 1991, the refuge manager stated that since the completion of the mitigation structures, the Service had expended over \$50,000 on maintenance.
- 5. <u>History of Project Alterations by Local Interests Since Project Completion</u>.
- A. The Service had to replace the deteriorated 36" cmp in Area 1. The existing pipe and downstream headwall were both removed. As an economy measure, rip rap protection was provided in lieu of replacing the headwall.
- B. When Levee A at Prosperous Bayou (Area 3) was lost, the Service moved inland to build a new temporary levee and protected it and the rebuilt gate structure with sheet pile headwalls. Later, after the levee became eroded, the Service placed rip rap on the White River face of the levee.
- C. After the original 36" cmp gate structure in Area 4 had deteriorated, the Service, due to fiscal restraints, replaced it with an unregulated 18" concrete pipe placed higher up near the top of the levee.
- D. After Levee A in Area 5 was lost, the Service constructed a temporary levee and gate structure inland in the southernmost slough.
- 6. <u>Proposed Corrective Measures</u>. The proposed methods of correcting design and construction deficiencies are shown on Plates 2 through 4. The corrective measures are described below:
- A. Area 1: Bring the existing sluice gates and slide gate to operable condition as described below and as shown.
- (1) Repair 60" sluice gate: Remove and reinstall floorstand; adjust existing guides; clean and paint two 60" gates, stems and floorstands; and, clean concrete on top of wall and patch spalls with grout.
- (2) Repair 36" slide gate: Install complete 36" slide gate on existing structure.
  - B. Area 2: None.
- C. Area 3: Abandon the existing gate structure (plug with concrete), restore the levee crown width, and provide stone slope protection as shown.
- (1) Widen a 100-foot length of levee along the same alignment to original width, that is, with a 10-foot crown width and specified side slopes. Provide quarry run stone on the slopes to resist erosion.

- (2) Since the gate structure and culvert are no longer used for reservoir A level control, the culvert will be plugged with concrete and abandoned in place.
- D. Area 4: Provide erosion protection along the levee and beyond each end of the 18" pipe in Levee A. See Plate 4.
- E. Area 5: Construct a 1,500-foot section of Levee A farther inland from the White River as shown on Plates 2 and 4.

#### 7. <u>Alternative Corrective Measures Considered</u>.

- A. Area 3: Abandon existing gate structure, culvert, and sheet pile headwalls. Alternatives considered included:
- (1) Seal both ends of pipe with a metal plate. This would leave a potential failure zone in the embankment and was therefore considered unacceptable.
- (2) Remove the gate structure and culvert from the embankment and rebuild the levee. This was considered to be too expensive.
- (3) Plug the culvert with concrete and abandon in place. This alternate was selected as being the most economical satisfactory fix.
- B. Areas 1,2,4 & 5: No practical alternatives were identified for consideration.
- 8. Estimated Cost of Corrective Measures. The estimated cost for all repairs at Areas 1,3,4, and 5 is \$261,393, including \$29,650 for E&D and \$16,200 for Supervision and Administration. See Cost Estimate Summary, Appendix C.
- 9. <u>Justification</u>. Rehabilitation of Corps constructed levees and structural features is desirable for the following reasons: (1) To correct design deficiencies, (2) to correct construction deficiencies, and (3) to fully comply with the original permit signed with the Service. These items are more fully described below:
- A. Area 1: The 60" sluice gate and 36" slide gate were identified as having design and construction deficiencies. These items should be expected to have a reasonable usable life, which has not been the case. The Service has had to expend considerable effort to be able to even marginally operate the structures by using stop logs or sand bags. These features have been unusable for many years and the Service has not been able to perform needed repairs having spent considerable funds on maintaining the levees. The sense of urgency should come from the Corps in a effort to mitigate damage to our reputation as experts in the fields of water resource facility design, management, and construction.

- Area 3: Abandon the existing gate structure as requested by the Service. Rebuild the eroded section of the levee to a 10 foot crown width and rip rap the White River face of the structure at Prosperous Bayou. A comparison of trip reports (87,88 and 90) and discussion with Service personnel emphasizes the urgency of the situation. The levees have deteriorated at an increasing rate that threatens the structural integrity of Levee A. The gate structure is in danger of being destroyed and with it goes the use of Reservoir A. This breach would provide access for White River flows down Prosperous Bayou. This would destroy Service ability to regulate and control water to the wildlife refuge and lead to increased erosion and destruction of wildlife and lands. Of greater concern to the Corps would be the frequent torrents of water that could flow down Prosperous Bayou toward the Arkansas Post Canal levee. This could lead to future expensive maintenance problems for the Corps.
- C. Area 4: Provide stone protection at the 18" cmp that was installed by the Service, located near the top of Levee A. Although this culvert was installed by the Service, it was a replacement for a (deteriorated) 36" cmp originally installed by the Corps. Accordingly, it is reasonable to expect the Corps to provide adequate stone protection (as desired by the Service) or for the Corps to provide a new 36" gate structure. Since the lower cost fix is acceptable to the Service, we should expeditiously complete this rehabilitation.
- D. Area 5: Construct a new 1,500 foot section of levee inland from the White River to replace that previously eroded. To comply with the permit with the Service, these mitigation structures were supposed to last as long as the Arkansas Post Canal, subject only to normal maintenance. The Service has provided adequate maintenance; however, the original facilities have not provided the required useful life.
- E. Legal Obligations: The failure of the mitigation features to fulfill our legal agreements with the Fish and Wildlife Service also makes the Corps technically out of legal compliance with the Fish and Wildlife Coordination Act and the National Environmental Policy Act. Without rehabilitation, one could advance a good position that the Corps is violating these laws and, should litigations ensue, the Corps would be exposed to unfavorable publicity especially since the problems are directly related to design and construction issues. It is, therefore, in the Nation's best interest to accomplish this work now.
- G. ER 1165-2-119: In applying the guidelines contained in ER 1165-2-119, it is important to note that the mitigation features were to operate for the life of the navigation project that traverses through the refuge. Compared with the adjacent navigation features, it is obvious that the failure of mitigation

features is attributable to a combination of design and construction deficiencies. Application of ER 1165-2-119 criteria is as follows:

- (1) The project does not function according to the agreements and intended purposes, nor are the features viable or operational.
- (2) The conditions and mitigation requirements have not changed. The features are essential to fulfill the authorized project purposes and various environmental laws.
- (3) Rehabilitation would bring the project into compliance with authorized purposes.
- (4) Rehabilitation costs associated with existing features are significantly less and incrementally justified compared with alternative measures that would be required.
- (5) Maintenance of the mitigation features is not the cause of failure. The Service keeps national wildlife refuges (such as the White River National Wildlife Refuge) well maintained and operational because of the high waterfowl usage. Since major rehabilitation of project features is now required, the costs greatly exceed the maintenance budget of the White River National Wildlife Refuge.
- 10. Cost Sharing. Not applicable. Under terms of the permit signed by the Corps and the Service, the levees and structural features that were constructed by the Corps were in payment for use of Service (Government) lands. There was no cost sharing per se. Instead, the Corps was required to mitigate damages to the wildlife refuge caused by the construction of the Arkansas Post Canal. There was no first cost for the Service, which was required only to provide future normal maintenance. Since the Corps did not fully construct the levees, roads, and other features in accordance with normal Corps design and construction standards and since the Corps did not comply with the terms of the permit, it is unreasonable to expect the Service to share in major rehabilitation costs.

#### 11. Environmental Considerations:


#### A. Introduction.


(1) The White River National Wildlife Refuge was established in the 1930's as a waterfowl refuge. The 139 channel scar lakes on the 115,000 acre refuge have furnished good sport and commercial fishing from the beginning. In the 1960's the refuge was opened to deer hunting for the first time and has been open yearly since. Squirrel hunting has always been opened for the first few days of squirrel season. Duck hunting in limited areas is now permitted for half-days, three days a week, during the state waterfowl season.

- (2) When the McClellan-Kerr Navigation System was constructed, the preferred route for the Arkansas Post Canal linking the Arkansas and White Rivers for navigation purposes was across the south end of the refuge. In exchange for the right-of-way across the land belonging to the Department of Interior, the Corps constructed three green-tree reservoirs, complete with levees and water control structures, to facilitate waterfowl management on the refuge. The Service agreed to operate and maintain the reservoirs after construction.
- (3) However, damage has occurred to one of the levees constructed by the Corps; damage that exceeds the expectation of ordinary maintenance. The concrete water-control structures have also shown damage which could not have been prevented by maintenance. As a result, the Corps has agreed to repair the structures and gates, and to restore the levee destroyed by erosion from the White River.
- B. Environmental Resources. The natural resources of the project area (Plates 1 and 2) are many and varied, and of considerable significance regionally. The green-tree reservoirs furnish excellent fishing, particularly in the springtime. In the fall, they furnish resting and feeding areas for all migratory waterfowl. The migrating eagles use the snags in the reservoirs for perching and watching for prey. Alligators are seen frequently in the sloughs and bayous encompassed by the reservoirs. Deer and turkey are common to abundant in the area. Furbearers such as beaver, muskrat, skunk, river otter, raccoon, and coyote are resident to the area. Occasionally seen are black bears, year 'round residents of the refuge. Over 200 species of song birds have been identified as residents and/or visitors to the area. In short, the area abounds with terrestrial and aquatic species of wildlife, and contributes to the area by providing hunting, fishing, birdwatching, wildlife photography, sightseeing, camping, and other opportunities.
- C. Cultural Resources. There are no recorded archeological sites in the immediate project area according to the records of the Arkansas Archeological Survey. A shipwreck located in the White River channel, upstream of the project area, should not be affected. Numerous archeological sites of the late prehistoric and early historic period are located in the surrounding area but they should not be affected by the project. Telephone coordination with the Arkansas State Historic Preservation Officer (SHPO) was conducted on 10 April 1991. The SHPO requested that all new borrow areas of areas to be impacted by levee construction should be surveyed for cultural resources. Archeological fieldwork has been delayed by high water levels in the project area.
- D. Environmental Compliance. Draft versions of the Environmental Assessment, Finding of No Significant Impact (FONSI), and Section 404 (b) (1) Evaluation Report are virtually

complete, but are not included in this report. A Section 404 Joint Public Notice (for the new levee section only) will be submitted at a later date in accordance with regulations. A Section 106 coordination letter will be sent to the Arkansas State Historic Preservation Officer (SHPO) following a reconnaissance of the 1500 foot levee replacement in Area 5, which will occur after the White River recedes.

12. <u>Recommendations</u>. Recommend that this report be approved as a basis for funding the design and rehabilitation of project features described herein. Additionally recommend that construction funds in the amount of \$261,393 be included in the FY93 Construction General Budget for this purpose.





## PENMIT TO THE

UNITED STATES CORPS OF ENGINEERS, DEPARTMENT OF THE ARMY
TO USE AND OCCUPY PROFERTY IN THE
WHITE RIVER MATIONAL WILDLIFE REFUGE, ARKANSAS

WIEREAS, the United States Bureau of Sport Fisheries and Wildlife and its predecessor agencies, herein referred to as the "Bureau", has acquired certain lands in fee title as the White River National Wildlife Refuge, Arkansas, for the benefit and protection of migratory birds and other forms of wildlife, and

MMEREAS, pursuant to the Rivers and Harbors Act of July 24, 1946, as amended, the U. S. Corps of Engineers, herein referred to as the "Corps", has been authorized to construct, maintain and operate the Arkansas River Navigation Canal Project, and

WHEREAS, the Corps, in connection with the Arkansas River Multiple-Purpose Project, proposes to locate and construct on the Refuge a portion of the navigation canal and Lock and Dam No. 1:

NOW, THEREFORE, to further the aims and purposes of the Arkansas River Multiple-Purpose Project, the Corps is bereby granted a permit to use and occupy 545 acres of Refuge land upon which it may construct, maintain, and operate said navigation canal and Lock and Dam No. It upon which it may locate a public access area as heretofore agreed, and upon which additional recreational or other facilities may be located in future years on mutual agreement of the Eureau and Corps. This permit to remain in effect for as long as these facilities are maintained and operated for purposes authorized in the above act. The area covered by this permit, which is for an indefinite period, is described below and shown in blue on attached map, Exhibit "A", which is made a part hereof.

### DESCRIPTION - PARCEL "A" - 545.00 Acres

A tract of land situated in the county of Arkansas, State of Arkansas, being a part of Sections 1, 2, and 3, Township 8 South, Range 2 West of the Fifth Principal Meridian, and being more particularly described as follows:

Beginning at a point on the west line of said Section 3, which is 1,040 feet north of the west quarter corner thereof, being on the west boundary line of the White River National Wildlife Refuge and being 610 feet north of Station 164+20 on

the centerline of the Mavigation Canal; thence southeasterly 2,120 feet to a point which is 635 feet north of Station 143400; thence southeasterly 2,000 feet to a point which is 645 feet north of Station 123+00; thence southwasterly 750 feet to a point which is 645 feet north of Starion 115450; thence southeasterly 450 feet to a point which is 660 feet north of Station 111+00; thence southeasterly 2,400 feet to a point which is 660 feet north of Station 87+00; thence southeasterly 1,780 feet to a point which is 650 feet north of Station 70+20; thence northeasterly 1,130 feet to a point ! which is 1,125 feet north of Station 59+85; thence southeasterly 2,775 feet, more or less, to a point on the ordinary highwater line, right bank of White River, which is 1,325 feet north of Station 32+00; thence southerly along the meanders of said ordinary high-water line to its intersection with a line extended southerly and perpendicular to Station 13+00; thence southwesterly along said line extended from Station 13+00 to its intersection with the south line of said Section 1; thence westerly along said south line 910 feet to a point on the southerly right-of-way line for said Navigation Canal, which is 800 feet south of Station 22-180; thence along said right-ofway line as follows north 74° 22' west 1,500 feet to a point; thence south 83° 50' west 1,080 feet to a point, said point being I,200 feet south of Station 46+50; thence north 747 727 west 5,210 feet to a point; thence north 07° 23" east 320 feet to a point which is 700 feet south of Station 100+00; thence north 82° 37' west 6,300 feet to a point on the west line of said Section 3; thence, departing from said right-of-way line, north along said section line 1,310 feet to the point of beginning, and containing 545.00 acres, more or less.

Also, to facilitate construction work, the Corps is permitted, for a period not to exceed five years after execution of this permit, to use and occupy an additional 80 acres of Refuge Land, as shown in red on map Exhibit "A" and described below:

#### DESCRIPTION - PARCEL "E" - 80.00 Acres

A tract of land situated in the county of Arkansas, State of Arkansas, being a part of Sections 1, 2, and 3, Township 8 South, Range 2 West of the Fifth Principal Meridian, and being more particularly described as follows:

Beginning at a point on the west line of smid Section 3, which is 1,040 feet north of the west quarter commer thereof,

being on the west boundary line of the White River National Wildlife Refuge and being 610 feet north of Station 164+20 on the centerline of the Navigation Canal; thence southeasterly 2,120 feet to a point which is 635 feet north of Station 143+00 on said centerline; thence southeasterly 2,000 feet to a point which is 645 feet north of Station 123+00 on said centerline; thence southeasterly 750 feet to a point which is 645 feet north of Station 1154-50; thence southeasterly 450 feet to a point which is 660 feet north of Station 111+00; thence southeasterly 2,400 feet to a point which is 660 feet north of Station 87+00; thence southeasterly 1,780 feet to a point which is 650 feet north of Station 70+20; thence northeasterly 1,130 feet to a point which is 1,125 feet north of Station 59+85; thence southeasterly 2,775 feet, more or less, to a point on the ordinary high-water line, right bank of White River, which is 1,325 feet north of Station 32+00; thence northerly along the meanders of said ordinary high-water line 275 feet to a point! which is 1,600 feet north of Station 33+00; thence northwesterly 2,725 feet to a point which is 1,360 feet north of Station 60-100; thence southwesterly 1,130 feet to a point which is 900 feet north of Station 70435; thence northwesterly 1,785 feet to a point which is 900 feet north of Station 87+00; thence north 50 feet to a point which is 950 feet north of said Station 87+00; thence northwesterly 5,600 feet to a point which is 950 feet north of Station 143+00; thence south 150 feet to a point which is 800 feet north of said Station 143+00; thence northwesterly 2,140 feet to a point on the west line of said Section 3, which is 800 feet north of Station 164+40; thence south along said west line 190 feet to the point of beginning, and containing 80.00 acres, more or less.

In consideration of this permit granted by the Bureau, the Corps as a part of project costs agrees:

- 1. To construct necessary levees and control structures to create Reservoirs A and B on Refuge land immediately north of the navigation canal for management by the Bureau in their waterfowl program. Construction items for these two reservoirs are to include:
  - a. Controllable inlet and diversion from Pool No. 2 designed to supply water at a rate of 150 c.f.s. for gravity delivery to White River National Wildlife Refuge.

- b. Diversion Ditch "A" designed to convey water supply from inlet structure to the interceptor drainage ditch.
- c. Interceptor Drainage Ditch, a project feature comprised of sections "B" and "C", designed to convey waters from the 28.1 square mile drainage area of Boney Locust Bayou to White River and also water supply for wildlife purposes.
- d. Control Structure in Interceptor Drainage Ditch between sections "B" and "C" designed to impound Reservoir "B" and also to divert water into Reservoir "A". Access roadway from project retaining levee would be incorporated in this structure. The section of the structure in the drainage ditch should have stoplog spillway sections for controlled upstream impoundment to elevation 148 feet m.s.l. in Reservoir "B". Structure openings should be of adequate size to provide prompt evacuation of storm drainage. Maximum length of ponding of storm runoff shall be four days.
- e. Diversion Ditch "D" designed to convey water from the main control structure to Reservoir "A".
- f. Levce section separating Reservoir "A" on the south end from the interceptor drainage ditch. It would be constructed to about elevation I4I feet.
- g. Two water-control structures in south retaining levee at crossings of Wild Goose Bayou.
- h. Intermittent levee sections along bank of White River to about elevation 141 feet m.s.l. for Impounding Reservoir "A".
- i. A stoplog water-control structure in the levee section constructed across the mouth of Laboring Bay.
- j. A water-control structure in the levee section to be constructed across Paradise Bayou.
- k. Levee sections separating Reservoirs "A" and "B". This levee would extend north from the main control structure and would be constructed to about elevation 150 feet m.s.l. Total length would be about 22,780 feet.

The Fish and Wildlife Plan, which includes the location and layout of the above construction features, is shown on attached Exhibit "B", and is made a part hereof.

- 2. To operate and maintain a water diversion structure at Lock No. 2; to permit the Bureau to withdraw from pool at said lock sufficient water to properly manage Reservoirs A and B. The total annual diversion is estimated to be approximately 10,000 acre feet of water, which, if necessary, may be diverted to Reservoirs A and B within a 30-day period. The diversion is to be coordinated with the navigation locking requirements which will be given first priority.
- 3. To close the public access area at Lock and Dam No. 1 between November 1 and March 15 of any year if requested to do so by the Regional Director, Bureau of Sport Fisheries and Wildlife.
- 4. To use and occupy the area without cost or expense to the Bureau.
- 5. To maintain the area in good condition and repair.
- 6. To protect the property from fire and vandalism. Also, it shall make and enforce such rules and regulations as are necessary, within its legal authority, to exercise the privileges granted in this permit.
- 7. To report to the Bureau any interference with or damage to any refuge property described herein arising from the exercise of privileges herein granted, and further, that it will correct any such interference or damage to the satisfaction of the Regional Director, Bureau of Sport Fisheries and Wildlife.
- 8. That the Bureau, its employees, agents, and assigns may at all times have full rights of access to and through said area for any work whatever involving Bureau operations or wildlife management and protection.
- 9. That in granting this permit the intent of the Bureau is to convey to the Corps only those rights necessary to (1) operate, use, and maintain the navigation canal, (2) operate, use and maintain Lock and Dam No. 1, and (3) operate, use, and maintain the public access area at Lock and Dam No. 1. All other rights, and especially those relating to fish and wildlife, are reserved to the Bureau.

In connection with the operation and maintenance of fish and wildlife features of the project, as provided herein and shown on Exhibit "B", the Corps and Bureau mutually agree that:

- 10. The Corps shall operate and maintain the water diversion structure at Lock No. 2.
- 11. The Burenu shall operate and maintain all other structures, ditches and levees incident to the management of Reservoirs A and B.
- 12. In the event water is needed for the proper management of Reservoirs A and B, and the Corps is unable to provide the necessary operating service, the Bureau may on a temporary emergency basis operate all water control structures leading to Reservoirs A and B--including those at Lock No. 2, after obtaining assurance from the District Engineer or his authorized representative that the Corps is unable to provide the necessary operating service at the time requested.
- 13. Any signs constructed by the permittee involving public access, recreation, or both, shall give full recognition to the United States Fish and Wildlife Service on the cooperative nature of the land development.

OCT 11963

(Date)

Regional Director, Bureau of Sport
Fisheries and Wildlife

CHARLES D. MAYING J. Colonel, CE

District Engineer, U. S. Army Engineer
District, Little Foods

Recard Cy of Parmet Drawing blut Hickoriese in Real Estate Files

## HISTORY OF PROJECT DEFICIENCIES White River National Wildlife Refuge (McClellan-Kerr Arkansas River Navigation System)

- 1. On 29 August 1967, the Service provided a letter of inspection and acceptance of the mitigation features which noted that current velocity along the White River had increased significantly due to channelization on the lower White River below the Arkansas Post Canal. The resulting erosion had endangered Levee A, which was constructed by the Corps in connection with other mitigation measures on the refuge. The Corps was requested to take immediate steps to provide bank stabilization for those portions of the White River subject to this greatly increased erosion. (This requested work was not accomplished by the Corps.)
- Reference: Fish and Wildlife Service Memo, 23 April 1987.
- A. Areas 3,4 & 5 (See Encl 2, Plate 2): "In at least two places, on the right descending bank of the White River in the vicinity of RM 13.5 (Area 3) and between miles 10 to 12 (Areas 4 & 5), there is considerable danger of the complete loss of Levee A due to headcutting during high river flow. Only through temporary repairs has the Service prevented the headcut near mile 13.5 from dewatering the Levee A greentree impoundment."
- B. Area 1: "An additional problem exists at the southern end of "Levee B" where two separate water control structures were constructed. The larger of the two structures consists of two separate pipes and drop gates; the smaller is only one pipe and drop gate. At the present time, apparently due to settling and cracking, the concrete wall on the larger structure is broken and one of the drop gates cannot be raised to dewater the Levee B impoundment. The dropgate on the smaller structure has broken off and an improvised stop log system is utilized. Although functional, this improvised system is not nearly so efficient as the original drop gate and requires extensive time and labor to operate and maintain."
- 3. Reference: Fish and Wildlife Service Memo, 20 May 1988. "The Fish and Wildlife Service is becoming increasingly concerned over the deteriorating condition of Greentree reservoir levees A, B, and C and the associated water control structures. ....the levees and pipe/drop structures will require major rehabilitation."
- 4. CESWL-PL-A (CESWL-PL/2 Aug 88) 2nd End stated, "We find that the project has not fulfilled the needs for which it was conceived and constructed. This failure to fulfill the needs is due to design and construction shortcomings in providing the

water control structures. The failure of the levee is due to normal occurrences. We also find that the ordinary maintenance by the US Fish and Wildlife Service has been adequate."

- 5. A CESWL-ED-DP trip report dated 8 December 1988 described the following results of an 18 November 1988 District inspection:
- Area 1 contains two gate structures which pass water through Levee B. The first structure consists of 2-60" concrete pipes with concrete headwalls, stop logs and slide gates. north gate is inoperable. Apparently the contraction and expansion of the soils in the area has shifted the structure to the point where the gate shaft is binding and prevents operation of the gate. Concrete has broken and/or spalled off of the headwall around the gate support bracket and an anchor bolt is broken. The anchor bolt broke in 1984 and the sliding gate shaft was in a bind for several years before 1984. After the anchor bolt broke, it could no longer be lowered, so they have used stop logs since. The second structure on Levee B is approximately 100 feet north of the first structure. It consists of 1-36" CMP with concrete headwalls, stop logs and a slide gate. The slide gate on the structure has been missing since at least 1978.
- B. "Area 2 is vastly different that the 1967 quad map shows. Levee A in this area in completely gone as is the access road that the Service used to maintain all of Levee A. It appears the White River has meandered inland 400± causing extensive bank caving as it progressed. Currently at high river stages the White River is developing a channel and entering into Prosperous Bayou...... If this continues, it could prove disastrous for the refuge and navigation on the White River."
- C. Area 3. "The original structure consisted of 1-36" CMP with concrete headwalls and stop logs. That structure and parts of Levee A were lost due to bank caving. When this was lost, the use of reservoir A was also lost. The Service moved inland and constructed a new levee section to plug the hole and a gate structure so Reservoir A could be put back into service. The sheet pile headwalls were installed to protect the levee and gate structures from erosion. Flood waters currently overtop the levee and are causing erosion from behind the sheet piles. The result is a distressed condition on the levee slope with a potential for a breach. Currently the road across the structure in only 5 feet wide making it almost impassible."
- D. "Area 4 was not visited on this trip. The Service poured two concrete spillways in 1981 through Levee A north and south of Area 4 and placed rip-rap along the levee for protection. This was done to reduce the severe headcutting of Levee A during high water."
- E. Levee A presently ends at Area 5. There is no longer a connection road along Levee A to Wild Goose landing because a large section of the levee had been eroded away."

- 6. Reference: CESWD-PL-R Memorandum, 5 July 1988.
- A. ".... it appears that the FWS refuge people may have a very reasonable request for the Corps to repair the mitigation features."
- B. It appears that the Corps "made structural and design changes in the mitigation features without consulting FWS. Additionally, it looks like we (Corps) underestimated the altered flow velocities and subsequent under designed the mitigation features."
- 7. Reference: CESWL-ED-DG Memorandum, 18 September 1989.
- A. Area 1: "It is our belief that the failure of the two gates, one 60" sluice gate and one 36" slide gate, is due to design and construction deficiencies. The concrete has spalled at the support bracket on the 60" sluice gate apparently due to poor concrete. The 36" slide gate has popped off."
- B. Area 3: The large lengths of levee A that have caved into the White River have done so as a normal occurrence. These levees have not been lost as a result of lack of maintenance by the service. In fact, the Service has done a lot of work in repairing and maintaining the levees. When the levee at Prosperous Bayou (Area 3) was lost, the Service moved inland to build a new levee and protected the levee and gate structure with sheet pile headwalls. This structure is now in danger of being lost and with it goes the use of Reservoir A. This breach would provide access for White River flows down Prosperous Bayou."
- C. Area 4: The Service has replaced a blow-out and added some rip-rap in this area.
- D. "Recommendation: As a replacement to the Wildlife Service, we recommend that the Corps repair the above gates, fill and rip-rap the White River face of the structure at Prosperous Bayou. It is in the Corps' best interest to do the work in exchange for Wildlife Service lands that are used for dredge disposal on the lower White River."
- 8. Reference: CESWL-PL-R Memorandum For Record, 8 February 1991.
- A. Area 1 Verified inoperable condition of the north 60" sluice gate. The 36" slide gate was inoperable. Flow was controlled by use of a stop log. A Service representative stated that they had replaced the deteriorated 36" pipe through Levee B the previous summer.
- B. Area 2 This area had been severely eroded by the White River. No additional work was requested since it was not constructed by the Corps.

- C. Area 3 Verified condition of the eroded levee.
- D. Area 4 Examined an area where the Service had inserted an 18" pipe near the top of Levee A to speed drainage of Reservoir A.
- E. Area 5 The Service representative indicated that approximately 900 feet of Levee A had been washed out and he suggested that a new section of levee be constructed farther back from the river.

March 28 APRIL 1991

CESWL-ED-C

MENORANDUM FOR: Chief, Planning Division, Project Reports Br.

Attn: Terry Daniel

Request for Revised Cost Estimate, Reconnaissance Report to Correct Design and Construction Deficiencies at the White SUBJECT:

River National Refuge, Arkansas

The revised cost estimate is inclosed. It includes the scope of as outlined in the memorandum dated 28 March 1991 (subject as above) provided to us by the Ch, Gen. Engr. Sec.

This estimate includes 7.85% for escalation and 25% contingincies on construction work. It also includes for the prime contractor 10% for FOOH, 5% for HOOH, 10% for profit and 1% for bond.

Encl 1

BILLY G. SMITH P.E.

Chief, Cost Engineering Branch

Randall R. Montgomery P.E. Cost Engr, Cost Engineering Branch TABLE OF CONTENTS

U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF WHITE RIVER WILDLIFE REFUGE TEST CONTENTS PAGE 1

SUMMARY	REPORTS	SUMMARY PAGE
PROJECT	OWNER SUMMARY - LEVEL 1	
PROJECT	OWNER SUMMARY - LEVEL 2	
PROJECT	OWNER SUMMARY - LEVEL 3	
PROJECT	OWNER SUMMARY - LEVEL 4	6
PROJECT	OWNER SUMMARY - LEVEL 5	11
PROJECT	OWNER SUMMARY - LEVEL 6	17
PROJECT	INDIRECT SUMMARY - LEVEL 1	27
PROJECT	INDIRECT SUMMARY - LEVEL 2	28
PROJECT	INDIRECT SUMMARY - LEVEL 3	29
PROJECT	INDIRECT SUMMARY - LEVEL 4	
PROJECT	INDIRECT SUMMARY - LEVEL 5	
PROJECT	INDIRECT SUMMARY - LEVEL 6	43
	DIRECT SUMMARY - LEVEL 1	
PROJECT	DIRECT SUMMARY - LEVEL 2	54
PROJECT	DIRECT SUMMARY - LEVEL 3	55
PROJECT	DIRECT SUMMARY - LEVEL 4	58
PROJECT	DIRECT SUMMARY - LEVEL 5	63
	DIRECT SUMMARY - LEVEL 6	
CONTRAC	TOR INDIRECT SUMMARY	
CONTRAC	TOR INDIRECT SUMMARY - LEVEL 1	80
CONTRAC	TOR INDIRECT SUMMARY - LEVEL 2	
CONTRAC	TOR INDIRECT SUMMARY - LEVEL 3	
	TOR INDIRECT SUMMARY - LEVEL 4	
	TOR INDIRECT SUMMARY - LEVEL 5	
CONTRAC	TOR INDIRECT SUMMARY - LEVEL 6	

### DETAILED ESTIMATE

DETAIL PAGE

TIME 14:57:27

- O. Project Distributed Costs
- 11. LEVEES AND FLOODWALLS
  - LEVEES
    - 1. MOBILIZATION AND DEMOBILIZATION
      - 1. LOAD AND UNLOAD EQUIPMENT TO BE
      - 2. TRANSPORT EQUIPMENT (MOB & DEMOB
      - 3. MOB & DEMOB EQPMT TO BE DRIVEN,
    - 2. REPAIR 60" SLUICE GATES
      - B. METALS
        - 1. REMOVE EXISTING 60" SLUICE GATES
        - 3. CLEAN AND PAINT GATE
        - 5. ADJUST EXISTING GATE GUIDES
        - 7. INSTALL 60" SLUICE GATE
        - 8. REPAIR SPALLED CONCRETE
        - 9. METAL WORK FOR IN-OPERABLE GATE
    - 3. REPLACE 36" SLIDE GATE
      - B. METAL WORK
        - 1. Rem Ext 36" Slide Gate & Framewk
        - 3. Install New 36" Slide Gate
    - 4. ELINMINATE GATE STR & REPR LEVEE

# PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF WHITE RIVER WILDLIFE REFUGE TEST

TABLE OF CONTENTS

CONTENTS PAGE 2

DETAILED ESTIM	ATE	DETAIL	PAGE
1 2 4 5	ITE WORK  . CLEAR AND GRUB  . EXC, PL, COMPACT & GRADE FILL  1. EXCAVATE AND PLACE NEW FILL MAT.  2. INSTALL GEOTEXTILE MATERIAL.  3. SPREAD AND SHAPE TO GRADE.  4. COMPACTION.  5. CHECK GRADE.  . HAUL & DUMP RIPRAP ON WORK SITE  . PLACE RIPRAP ON SLOPES  . ESTABLISH TURF ON TOP OF LEVEE  1. Replace Top Soil.  2. Till or Prepare Seedbed.		1213131414
	3. Seed and Fertilize  ONCRETE . PREPARE CULVERT TO RECEIVE CONC		15
E. M	. PLACE CONC PLUG IN CULVERT ETALS . REMOVE EXISTING GATE STRUCTURE		
5. REPA B. S 1 3	IR 60' OF LEVEE & ADD RIPRAP  ITE WORK  . CLEAR AND GRUB . EXC, PL, COMPACT & GRADE FILL  1. EXCAVATE AND PLACE FILL MATERIAL . INSTALL GEOTEXTILE MATERIAL . SPREAD AND SHAPE TO GRADE COMPACTION CHECK GRADE HAUL RIPRAP FROM QUARRY TO SITE . PLACE QUARRY RUN STONE . ESTABLISH TURF ON LEVEE CROWN 1. Replace Top Soil Prepare Seed Bed.		19192020
1 2 3 4 5 6 6. CONS B. C	3. Seeding and Fertilizer  ONCRETE SPILLWAY WORK  . PREPARE SURFACE AREA TO RECEIVE  . PLACE FORMS FOR CONCRETE SPILLWY  . PLACE WWF (W6 X 6) IN SPILLWAY  . PLACE CONCRETE IN SPILLWAY  . FINISH CONCRETE IN SPILLWAY  . CURE CONCRETE IN SPILLWAY  T 1500 LF OF LEVEE  ONST 1500 LF OF LEVEE  . CLEAR AND GRUB		
	CONST 1500 LF OF LEVEE  1. Exc, Haul & Place fill		26

U.S. Army Corps of Engineers

TIME 14:57:27

TABLE OF CONTENTS

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

CONTENTS PAGE 3

DETAILED	EST.	IMATE
----------	------	-------

DETAIL PAGE

	5.	Check Gr	ade.				 		 	27
5.	EST	ABLISH 1	URF							
	1.	Replace	and S	Spread	Top	Soil.	 	. <b></b>	 	28
	2.	Prepare	Seed	Bed			 		 	28
	3.	Seeding	and F	Fertili	zing		 		 	29

### 30. ENGINEERING AND DESIGN

- B. ENGRG & DESIGN PRIOR TO 03-28-91
  - 2. ENGR SUPERVISION & REVIEW
  - 4. DESIGN BY THIS DISTRICT
  - 7. RECONN & DETAIL PROJECT REPORTS
- H. PLANS AND SPECIFICATIONS
  - L. BIDABILITY, CONSTRUCTIBILITY AND
- J. ENGINEERING DURING CONSTRUCTION
  - 1. AE CONTR AWARD/ADMINISTRATION
  - 3. VALUE ENGRG CH PROPOSALS (VECP)
  - 5. PERIODIC INSPECTIONS
- M. COST ENGINEERING
- N. CONST & SUPPLY CONTR AWARD ACTV
  - 1. PREPARATION OF BID DOCUMENTS
  - 2. CONTRACT NEGOTIATIONS
  - 3. CONTRACTING OFFICE ACTIVITIES
- T. PED PHASE LCPM
- 31. SUPERVISION AND ADMINISTRATION
  - B. CONTRACT ADMINISTRATION
    - 1. PRE-AWARD ACTIVITIES
    - 5. PROGRESS AND COMPLETION REPORTS
  - C. BENCH MARKS AND BASELINES
  - D. REVIEW OF SHOP DRAWINGS
  - E. INSPECTION AND QUALITY ASSURANCE
    - 1. SCHEDULE COMPLIANCE
    - 2. COMPLIANCE SAMPLING AND TESTING
  - F. PROJECT OFFICE OPERATION
  - H. CONTR INIT CLAIMS & LITIGATIONS
  - T. CONSTRUCTION PHASE LCPM

No Backup Reports...

\* \* \* END TABLE OF CONTENTS \* \* \*

U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

TIME 14:57:27

TITLE PAGE 1

.....

WHITE RIVER NATIONAL WILDLIFE REFUGE, REHABILITATION OF DETERIORATING STRUCTURES, RECONNAISSANCE REPORT

Designed By: LITTLE ROCK DIST CORP OF ENGR Estimated By: COST ENGINEERING BRANCH

Prepared By: RANDY MONTGOMERY

Date: 03/21/91

M - C A C E S G O L D E D I T I O N

Composer GOLD Copyright (C) 1985, 1988, 1990

by Building Systems Design, Inc.

Release 4.84

TITLE PAGE 2

This revised cost estimate is for "Reconnaissance Report to Correct Design and Construction Deficiencies at the White River National Refuge, Arkansas".

This estimate uses 10% for FOOH, 5% for HOOH, 10% for profit and 1% for bond charged to the prime contractor. Subcontractors were not used in the cost estimate.

An escalation of 7.85% and a 25% contingency was applied to this estimate.

This cost estimate is based on the following scope of work:

1. Repair 60 inch sluice gate:

PROJECT WRRFGH:

- a. Clean and paint both 60 inch sluice gates.
- b. Adjust existing guides on bothe 60 inch sluice gates.
- c. On the 60" gate theat is inoperable raise the floorstand and support it on two 9 ft L6x6x3/4 spanning across the top of the concrete headwall. Anchor the steel angles into the concrete headwall with wedge anchors. Attach the floorstand support bracket to the angles with steel bolts or weld.
- d. Repair the broken and spalled concrete caused by the cantilevered support bracket with grout.
- 2. Replace 36 inch slide gate:
  - a. Install new 36 inch slide gate on existing structure.
- 3. Eliminate existing gate structure and repair 100 lf of levee:
  - a. Plug existing  $36^{\text{\tiny{II}}}$  CMP with 2 ft of concrete on each end. Use 3.14~cy of concrete.
  - b. Clear and grub 0.34 acres.
  - c. Compact 2,625 cy of fill to 1V:4H sideslopes.
  - d. Place 2,470 tons of quarry run stone 2 1/2 ft thick on both sides of the levee.
  - e. Establish 0.02 acres of turf on the levee crown and all other disturbed areas lacking stone protection.
- 4. Laboring Bay Repair 60 lf of existing levee and 18" CMP and add stone protection.
  - a. Clear and grub 0.07 acres.
  - b. Compact 150 cy of fill.
  - c. Add 2 1/2 ft (530 tons) of quarry run stone protection on both sides of the levee and drainage channel.
  - d. Place 3.06 cy of concrete and 165 sf of WWF in slab spillways.
  - e. Establish 0.03 acres of turf on crown and all disturbed areas where stone protection is lacking.
- Construct approx. 1,500 lf of levee with compacted fill using 1V:4H side slopes. This will replace an orig levee that was washed out.
  - a. Clear and grub 1.44 acres.
  - b. Place and compact 4,400 cy of fill.
  - c. Establish 1.44 acres of turf.

# U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

SETTINGS PAGE 14

TIME 14:57:27

\*\* CONTRACTOR SETTINGS \*\*

AMOUNT PCT PCT'S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

A PRIME CONTRACTOR

PRIME CONTRACTOR OVERHEAD	P	10.00
PRIME CONTRACTOR HOME OFFICE OVERHEAD	P	5.00
PRIME CONTRATCTOR PROFIT	Р	10.00
PRIME CONTRACTOR BOND	Р	1.00

U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF WHITE RIVER WILDLIFE REFUGE TEST

TIME 14:57:27

SUMMARY PAGE 1

\*\* PROJECT OWNER SUMMARY - LEVEL 1 \*\*

QUANTY UOM CONTRACT ESCALATN CONTNGCY TOTAL COST UNIT

11 LEVEES AND FLOODWALLS 159,887 12,547 43,109 215,543 30 ENGINEERING AND DESIGN 29,650 0 0 29,650 31 SUPERVISION AND ADMINISTRATION 16,200 0 0 16,200 WHITE RIVER NATIONAL WILDLIFE 205,737 12,547 43,109 261,393

fri 29 Mar 1991

U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF
WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT OWNER SUMMARY - LEVEL 6 \*\*

SUMMARY PAGE 17

TIME 14:57:27

		QUANTY UOM	CONTRACT	ESCALATN	CONTNGCY	TOTAL COST	TINU
11 LEVEES A	AND FLOODWALLS					• • • • • • • • • • • • • • • • • • • •	
11.1 LEVEES	3						
11.1.1 MOBI	LIZATION AND DEMOBILIZATION						
11.1.1.1 LC	DAD AND UNLOAD EQUIPMENT TO BE						
	LOAD AND UNLOAD EQUIPMENT TO BE	10.00 PCS	635	50	. 171	857	85.65
11.1.1.2 TR	ANSPORT EQUIPMENT (MOB & DEMOB						
	TRANSPORT EQUIPMENT (MOB & DEMOB	80.00 HRS				6,357	79.46
11.1.1.3 MO	B & DEMOB EQPMT TO BE DRIVEN,						
	MOB & DEMOB EQPMT TO BE DRIVEN,	8.00 HRS	743	58	200	1,002	125.23
	MOBILIZATION AND DEMOBILIZATION	•			1,643	8,215	
11.1.2 REPA	IR 60" SLUICE GATES						
11.1.2.B ME	TALS						
11.1.2.8.1	REMOVE EXISTING 60" SLUICE GATES						
	REMOVE EXISTING 60" SLUICE GATES	2.00 EA	919	72	248	1,239	619.74
11.1.2.8.3	CLEAN AND PAINT GATE						
	CLEAN AND PAINT GATE	2.00 EA	984	77	265	1,326	662.99
11.1.2.8.5	ADJUST EXISTING GATE GUIDES						
	ADJUST EXISTING GATE GUIDES	2.00 EA	514	40	138	692	346.17

U.S. Army Corps of Engineers
PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT OWNER SUMMARY - LEVEL 6 \*\*

TIME 14:57:27

SUMMARY PAGE 18

QUANTY UOM CONTRACT ESCALATN CONTNGCY TOTAL COST 11.1.2.B.7 INSTALL 60" SLUICE GATE -------INSTALL 60" SLUICE GATE 2.00 EA 460 36 124 620 309.87 11.1.2.8.8 REPAIR SPALLED CONCRETE 98 8 REPAIR SPALLED CONCRETE 26 11.1.2.B.9 METAL WORK FOR IN-OPERABLE GATE \_\_\_\_\_ 672 53 181 METAL WORK FOR IN-OPERABLE GATE 906 -----3,646 286 983 4,916 METALS 3,646 286 983 4,916 REPAIR 60" SLUICE GATES 11.1.3 REPLACE 36" SLIDE GATE 11.1.3.B METAL WORK 11.1.3.B.1 Rem Ext 36" Slide Gate & Framewk ...... 927 73 250 Rem Ext 36" Slide Gate & Framewk 1,249 11.1.3.B.3 Install New 36" Slide Gate 5,888 462 1,587 7,937 Install New 36" Slide Gate ...... 6,815 535 1,837 9,187 METAL WORK ...... 6,815 535 1,837 9,187 REPLACE 36" SLIDE GATE

11.1.4 ELINMINATE GATE STR & REPR LEVEE

11.1.4.B SITE WORK

U.S. Army Corps of Engineers TIME 14:57:27

72 6 19 97

SUMMARY PAGE 19

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT OWNER SUMMARY - LEVEL 6 \*\*

		QUANTY	LIOM	CONTRACT	ESCALATA	CONTRACT	TOTAL COST	 TINU
		QUANTT		CONTRACT			TOTAL COST	
11.1.4.B.1 CLEAR A	AND GRUB							
CLEAR	R AND GRUB			1,310	103	353	1,766	
11.1.4.B.2 EXC, PL	., COMPACT & GRADE FILL							
11.1.4.B.2.1 EXCAV	ATE AND PLACE NEW FILL MAT	2625.00	CY	4,549	357	1,227	6,133	2.34
	ALL GEOTEXTILE MATERIAL	3878.00	SY	8,762	688	2,362	11,811	3.05
11.1.4.B.2.3 SPREA	AD AND SHAPE TO GRADE	2625.00	CY	1,901	149	512	2,562	0.98
11.1.4.B.2.4 COMPA	AD AND SHAPE TO GRADE ACTION C GRADE	2625.00	CY	1,231	97	332	1,659	0.63
11.1.4.B.2.3 CHECK	CORADE	2023.00	Li				212	0.08
EXC,	PL, COMPACT & GRADE FILL	2625.00	CY	16,599	1,303	4,475	22,377	8.52
11.1.4.B.4 HAUL &	DUMP RIPRAP ON WORK SITE							
HAUL	& DUMP RIPRAP ON WORK SITE	2470.00	TON	54,593	4,284	14,719	73,597	29.80
11.1.4.B.5 PLACE R	RIPRAP ON SLOPES							
PLACE	E RIPRAP ON SLOPES	2470.00	TON	15,661				8.55
11.1.4.B.9 ESTABLI	ISH TURF ON TOP OF LEVEE							
11.1.4.B.9.1 Repla	ace Ion Soil	17 00	CY	178	14	48	241	14,15
	or Prepare Seedbed	871.00		89	7	24	120	
11.1.4.B.9.3 Seed		97.00		16	1	4	21	0.22
ESTAE	BLISH TURF ON TOP OF LEVEE	871.00	SF	283	22	76	381	0.44
SITE	WORK			88,447	6,941	23,847	119,234	
11.1.4.C CONCRETE								
11.1.4.C.1 PREPARE	CULVERT TO RECEIVE CONC							

PREPARE CULVERT TO RECEIVE CONC

# U.S. Army Corps of Engineers PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST
\*\* PROJECT OWNER SUMMARY - LEVEL 6 \*\*

SUMMARY PAGE 20

TIME 14:57:27

		QUANTY UOM	CONTRACT	ESCALATN	CONTNGCY	TOTAL COST	UN I 1
11.1.4.C.3 P	LACE CONC PLUG IN CULVERT						
	PLACE CONC PLUG IN CULVERT	3.14 CY	674	53	182	908	289.26
	CONCRETE					1,005	
11.1.4.E MET	ALS						
11.1.4.E.1 R	EMOVE EXISTING GATE STRUCTURE						
	REMOVE EXISTING GATE STRUCTURE		460	36	124	620	
	METALS		460	36		620	
	ELINMINATE GATE STR & REPR LEVEE					120,860	
11.1.5 REPAI	R 60' OF LEVEE & ADD RIPRAP						
11.1.5.B SIT	E WORK						
11.1.5.B.1 C	LEAR AND GRUB						
	CLEAR AND GRUB		270	21	73	364	
11.1.5.B.3 E	XC, PL, COMPACT & GRADE FILL						
	EXCAVATE AND PLACE FILL MATERIAL		260	20	70	350	2.3
	INSTALL GEOTEXTILE MATERIAL	222.00 SY	526	41	142	709	3.1
	SPREAD AND SHAPE TO GRADE	150.00 CY	109 70	9	29 19	146 95	0.9
11.1.5.B.3.4 11.1.5.B.3.5		150.00 CY 150.00 CY	70 9	1	2	12	0.0
	EXC, PL, COMPACT & GRADE FILL	150.00 CY	974	76	263	1,313	8.7
11.1.5.B.4 H	AUL RIPRAP FROM QUARRY TO SITE						

# U.S. Army Corps of Engineers

TIME 14:57:27

SUMMARY PAGE 21

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT OWNER SUMMARY - LEVEL 6 \*\*

..... QUANTY UOM CONTRACT ESCALATN CONTNGCY TOTAL COST UNIT 11.1.5.B.5 PLACE QUARRY RUN STONE **530.00 TON 3,360 264 906 4,530 8.55** PLACE QUARRY RUN STONE 11.1.5.B.7 ESTABLISH TURF ON LEVEE CROWN 11.1.5.B.7.1 Replace Top Soil 24.00 CY 252 20 68 340 14 15 134 36 11.1.5.B.7.2 Prepare Seed Bed 1307.00 SF 180 10 0.14 11.1.5.B.7.3 Seeding and Fertilizer 145.00 SY 23 2 6 31 0.22 ------409 32 110 551 ESTABLISH TURF ON LEVEE CROWN \*\*\*\*\*\*\*\*\*\* SITE WORK 16,727 1,313 4,510 22,550 11.1.5.C CONCRETE SPILLWAY WORK 11.1.5.C.1 PREPARE SURFACE AREA TO RECEIVE PREPARE SURFACE AREA TO RECEIVE 350.00 SF 181 14 49 243 0.70 11.1.5.C.2 PLACE FORMS FOR CONCRETE SPILLWY 148 12 40 PLACE FORMS FOR CONCRETE SPILLWY 160.00 LF 199 1.25 11.1.5.C.3 PLACE WWF (W6 X 6) IN SPILLWAY PLACE WWF (W6 X 6) IN SPILLWAY 350.00 SF 129 10 35 173 0.50 11.1.5.C.4 PLACE CONCRETE IN SPILLWAY PLACE CONCRETE IN SPILLWAY 3.06 CY 357 28 96 481 157.19 11.1.5.C.5 FINISH CONCRETE IN SPILLWAY FINISH CONCRETE IN SPILLWAY 350.00 SF 87 7 23 117 0.33

U.S. Army Corps of Engineers PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF WHITE RIVER WILDLIFE REFUGE TEST

TIME 14:57:27 SUMMARY PAGE 22

159,887 12,547 43,109 215,543

\*\* PROJECT OWNER SUMMARY - LEVEL 6 \*\* QUANTY UOM CONTRACT ESCALATN CONTNGCY TOTAL COST 11.1.5.C.6 CURE CONCRETE IN SPILLWAY -----CURE CONCRETE IN SPILLWAY 3.50 CSF 15 1 20 5.81 916 72 247 1,235 403.48 CONCRETE SPILLWAY WORK 3.06 CY ...... 17,643 1,385 4,757 23,784 REPAIR 60' OF LEVEE & ADD RIPRAP 11.1.6 CONST 1500 LF OF LEVEE 11.1.6.B CONST 1500 LF OF LEVEE 11.1.6.B.1 CLEAR AND GRUB 1.44 ACR 5,548 435 1,496 7,479 5193.61 CLEAR AND GRUB 11.1.6.B.3 CONST 1500 LF OF LEVEE 598 7,625 11.1.6.B.3.1 Exc, Haul & Place fill 4400.00 CY 7,625 596 2,050 15,309 1,201 4,128 3.186 250 859 2,056 10,280 2.34 11.1.6.B.3.2 Apply Geotextile Material 6500.00 SY 20,638 3.18 3,186 250 4,295 0.98 11.1.6.B.3.3 Spread, and Shape to Grade 4400.00 CY 162 2,063 556 11.1.6.B.3.4 Compaction 4400.00 CY 2.781 0.63 263 71 355 21 0.08 4400.00 CY 11.1.6.8.3.5 Check Grade 38,348 CONST 1500 LF OF LEVEE 28,446 2,232 7,670 11.1.6.B.5 ESTABLISH TURF 923 72 249 1,244 1.07 11.1.6.B.5.1 Replace and Spread Top Soil 1162.00 CY 0.00 232 11.1.6.B.5.2 Prepare Seed Bed 62726 SF 172 14 46 948 6970.00 SY 74 256 1,278 0.18 11.1.6.B.5.3 Seeding and Fertilizing ...... ..... ...... 551 2,755 1913.03 ESTABLISH TURF 1.44 ACR 2.043 160 36,037 2,828 9,716 48,582 CONST 1500 LF OF LEVEE -----36,037 2,828 9,716 48,582 CONST 1500 LF OF LEVEE \_\_\_\_\_ 159,887 12,547 43,109 215,543

LEVEES

LEVEES AND FLOODWALLS

U.S. Army Corps of Engineers
PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

TIME 14:57:27

SUMMARY PAGE 23

400 0 0 400

50.00

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT OWNER SUMMARY - LEVEL 6 \*\*

QUANTY UOM CONTRACT ESCALATN CONTNGCY TOTAL COST 30 ENGINEERING AND DESIGN 30.B ENGRG & DESIGN PRIOR TO 03-28-91 30.B.2 ENGR SUPERVISION & REVIEW ENGR SUPERVISION & REVIEW 25.00 MHR 1,250 0 0 1,250 50.00 30.B.4 DESIGN BY THIS DISTRICT DESIGN BY THIS DISTRICT 200.00 MHR 10,000 0 0 10,000 50.00 30.B.7 RECONN & DETAIL PROJECT REPORTS 2,000 0 0 2,000 50.00 40.00 MRS RECONN & DETAIL PROJECT REPORTS ------13,250 0 0 13,250 ENGRG & DESIGN PRIOR TO 03-28-91 30.H PLANS AND SPECIFICATIONS 30.H.L BIDABILITY, CONSTRUCTIBILITY AND BIDABILITY, CONSTRUCTIBILITY AND 40.00 MHR 2,000 0 0 2,000 50.00 -----PLANS AND SPECIFICATIONS 2,000 0 0 2,000 30.J ENGINEERING DURING CONSTRUCTION 30.J.1 AE CONTR AWARD/ADMINISTRATION 400 0 0 400 50.00 AE CONTR AWARD/ADMINISTRATION 8.00 MHR 30.J.3 VALUE ENGRG CH PROPOSALS (VECP)

VALUE ENGRG CH PROPOSALS (VECP) 8.00 MHR

30.J.5 PERIODIC INSPECTIONS

U.S. Army Corps of Engineers
PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

TIME 14:57:27

SUMMARY PAGE 24

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT OWNER SUMMARY - LEVEL 6 \*\*

QUANTY UOM CONTRACT ESCALATN CONTNGCY TOTAL COST UNI

30.N.2 CONTRACT NEGOTIATIONS  CONTRACT NEGOTIATIONS 8.00 MHR 400 0 0 400 50.00  30.N.3 CONTRACTING OFFICE ACTIVITIES  CONTRACTING OFFICE ACTIVITIES 24.00 MHR 1,200 0 0 1,200 50.00  CONST & SUPPLY CONTR AWARD ACTV 2,400 0 0 2,400  30.T PED PHASE LCPM  PED PHASE LCPM  PED PHASE LCPM  96.00 MHR 4,800 0 0 4,800 50.00  ENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B CONTRACT ADMINISTRATION	 	QUANTY	UOM	CONTRACT	ESCALATN	CONTNGCY	TOTAL COST	TINU
ENGINEERING DURING CONSTRUCTION 3,200 0 0,3,200  30.M COST ENGINEERING 80.00 MHR 4,000 0 0 4,000 50.00  30.N CONST & SUPPLY CONTR AWARD ACTY  30.N.1 PREPARATION OF BID DOCUMENTS  PREPARATION OF BID DOCUMENTS 16.00 MHR 800 0 0 800 50.00  30.N.2 CONTRACT NEGOTIATIONS  CONTRACT NEGOTIATIONS  CONTRACTING OFFICE ACTIVITIES  CONTRACTING OFFICE ACTIVITIES  CONST & SUPPLY CONTR AWARD ACTY 2,400 0 0 2,400  30.T PED PHASE LCPM  PED PHASE LCPM  PED PHASE LCPM  PENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND AOMINISTRATION  31.3 CONTRACT ADMINISTRATION  31.3.1 PRE-AWARD ACTIVITIES								
30.M COST ENGINEERING  COST ENGINEERING 80.00 MHR 4,000 0 0 4,000 50.00  30.N. CONST & SUPPLY CONTR AWARD ACTY  30.N.1 PREPARATION OF BID DOCUMENTS  PREPARATION OF BID DOCUMENTS 16.00 MHR 800 0 0 800 50.00  30.N.2 CONTRACT NEGOTIATIONS  CONTRACT INEGOTIATIONS 8.00 MHR 400 0 0 400 50.00  30.N.3 CONTRACTING OFFICE ACTIVITIES  CONTRACTING OFFICE ACTIVITIES  CONST & SUPPLY CONTR AWARD ACTY 2,400 0 0 1,200 50.00  30.T PED PHASE LCPM  PED PHASE LCPM  PED PHASE LCPM  PENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B. CONTRACT ADMINISTRATION  31.B. CONTRACT ADMINISTRATION	PERIODIC INSPECTIONS	40.00	MHR	2,400	0	0	=	60.00
COST ENGINEERING 80.00 MHR 4,000 0 0 4,000 50.00  30.N. CONST & SUPPLY CONTR AWARD ACTY  30.N.1 PREPARATION OF BID DOCUMENTS  PREPARATION OF BID DOCUMENTS 16.00 MHR 800 0 0 800 50.00  30.N.2 CONTRACT NEGOTIATIONS  CONTRACT NEGOTIATIONS 8.00 MHR 400 0 0 400 50.00  30.N.3 CONTRACTING OFFICE ACTIVITIES  CONTRACTING OFFICE ACTIVITIES 24.00 MHR 1,200 0 0 1,200 50.00  CONST & SUPPLY CONTR AWARD ACTY 2,400 0 0 2,400  30.T PED PHASE LCPM 96.00 MHR 4,800 0 0 4,800 50.00  ENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B. CONTRACT ADMINISTRATION	ENGINEERING DURING CONSTRUCTION			3,200	0	0	3,200	
30.N. CONST & SUPPLY CONTR AWARD ACTV  30.N.1 PREPARATION OF BID DOCUMENTS  PREPARATION OF BID DOCUMENTS  16.00 MHR 800 0 0 800 50.00  30.N.2 CONTRACT NEGOTIATIONS  CONTRACT NEGOTIATIONS  8.00 MHR 400 0 0 400 50.00  30.N.3 CONTRACTING OFFICE ACTIVITIES  CONTRACTING OFFICE ACTIVITIES  CONTRACTING OFFICE ACTIVITIES  24.00 MHR 1,200 0 0 1,200 50.00  CONST & SUPPLY CONTR AWARD ACTV 2,400 0 0 2,400  30.T PED PHASE LCPM  PED PHASE LCPM  96.00 MHR 4,800 0 0 4,800 50.00  ENGINEERING AND DESIGN 29,650 0 0 29,650  31.SUPERVISION AND ADMINISTRATION  31.S. CONTRACT ADMINISTRATION	30.M COST ENGINEERING							
30.N.1 PREPARATION OF BID DOCUMENTS  PREPARATION OF BID DOCUMENTS 16.00 MHR 800 0 0 800 50.00  30.N.2 CONTRACT NEGOTIATIONS  CONTRACT NEGOTIATIONS 8.00 MHR 400 0 0 400 50.00  30.N.3 CONTRACTING OFFICE ACTIVITIES  CONTRACTING OFFICE ACTIVITIES 24.00 MHR 1,200 0 0 1,200 50.00  CONST & SUPPLY CONTR AMARD ACTV 2,400 0 0 2,400  30.T PED PHASE LCPM  PED PHASE LCPM 96.00 MHR 4,800 0 0 4,800 50.00  ENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B. CONTRACT ADMINISTRATION	COST ENGINEERING	80.00	MHR	4,000	0	0	4,000	50.00
PREPARATION OF BID DOCUMENTS 16.00 MHR 800 0 0 800 50.00  30.N.2 CONTRACT NEGOTIATIONS  CONTRACT NEGOTIATIONS 8.00 MHR 400 0 0 400 50.00  30.N.3 CONTRACTING OFFICE ACTIVITIES  CONTRACTING OFFICE ACTIVITIES 24.00 MHR 1,200 0 0 1,200 50.00  CONST & SUPPLY CONTR AWARD ACTV 2,400 0 0 2,400  30.T PED PHASE LCPM  PED PHASE LCPM  PED PHASE LCPM  PENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B. CONTRACT ADMINISTRATION  31.B.1 PRE-AWARD ACTIVITIES	30.N CONST & SUPPLY CONTR AWARD ACTV							
30.N.2 CONTRACT NEGOTIATIONS  CONTRACT NEGOTIATIONS 8.00 MHR 400 0 0 400 50.00  30.N.3 CONTRACTING OFFICE ACTIVITIES  CONTRACTING OFFICE ACTIVITIES 24.00 MHR 1,200 0 0 1,200 50.00  CONST & SUPPLY CONTR AWARD ACTV 2,400 0 0 2,400  30.T PED PHASE LCPM  PED PHASE LCPM  PED PHASE LCPM  96.00 MHR 4,800 0 0 4,800 50.00  ENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B CONTRACT ADMINISTRATION	30.N.1 PREPARATION OF BID DOCUMENTS							
CONTRACT NEGOTIATIONS 8.00 MHR 400 0 0 400 50.00  30.N.3 CONTRACTING OFFICE ACTIVITIES  CONTRACTING OFFICE ACTIVITIES 24.00 MHR 1,200 0 0 1,200 50.00  CONST & SUPPLY CONTR AWARD ACTV 2,400 0 0 2,400  30.T PED PHASE LCPM  PED PHASE LCPM 96.00 MHR 4,800 0 0 4,800 50.00  ENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B. CONTRACT ADMINISTRATION  31.B. CONTRACT ADMINISTRATION	PREPARATION OF BID DOCUMENTS	16.00	MHR	800	0	0	800	50.00
30.N.3 CONTRACTING OFFICE ACTIVITIES  CONTRACTING OFFICE ACTIVITIES 24.00 MHR 1,200 0 0 1,200 50.00  CONST & SUPPLY CONTR AWARD ACTV 2,400 0 0 2,400  30.T PED PHASE LCPM  PED PHASE LCPM 96.00 MHR 4,800 0 0 4,800 50.00  ENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B. CONTRACT ADMINISTRATION  31.B.1 PRE-AWARD ACTIVITIES	30.N.2 CONTRACT NEGOTIATIONS							
CONTRACTING OFFICE ACTIVITIES 24.00 MHR 1,200 0 0 1,200 50.00  CONST & SUPPLY CONTR AWARD ACTV 2,400 0 0 2,400  30.T PED PHASE LCPM  PED PHASE LCPM 96.00 MHR 4,800 0 0 4,800 50.00  ENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B CONTRACT ADMINISTRATION  31.B.1 PRE-AWARD ACTIVITIES	CONTRACT NEGOTIATIONS	8.00	MHR	400	0	0	400	50.00
CONST & SUPPLY CONTR AWARD ACTV 2,400 0 0 2,400  30.T PED PHASE LCPM  PED PHASE LCPM 96.00 MHR 4,800 0 0 4,800 50.00  ENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B. CONTRACT ADMINISTRATION  31.B.1 PRE-AWARD ACTIVITIES	30.N.3 CONTRACTING OFFICE ACTIVITIES							
CONST & SUPPLY CONTR AWARD ACTV 2,400 0 0 2,400  30.T PED PHASE LCPM  PED PHASE LCPM 96.00 MHR 4,800 0 0 4,800 50.00  ENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B CONTRACT ADMINISTRATION  31.B.1 PRE-AWARD ACTIVITIES	CONTRACTING OFFICE ACTIVITIES	24.00	MHR			0	1,200	50.00
PED PHASE LCPM 96.00 MHR 4,800 0 0 4,800 50.00 ENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B CONTRACT ADMINISTRATION  31.B.1 PRE-AWARD ACTIVITIES	CONST & SUPPLY CONTR AWARD ACTV					0	2,400	
ENGINEERING AND DESIGN 29,650 0 0 29,650  31 SUPERVISION AND ADMINISTRATION  31.B. CONTRACT ADMINISTRATION  31.B.1 PRE-AWARD ACTIVITIES	30.T PED PHASE LCPM							
31 SUPERVISION AND ADMINISTRATION  31.B CONTRACT ADMINISTRATION  31.B.1 PRE-AWARD ACTIVITIES	PED PHASE LCPM	96.00	MHR	4,800	0	0	4,800	50.00
31.B CONTRACT ADMINISTRATION  31.B.1 PRE-AWARD ACTIVITIES	ENGINEERING AND DESIGN			29,650	0	0	29,650	
31.B.1 PRE-AWARD ACTIVITIES	31 SUPERVISION AND ADMINISTRATION							
	31.B CONTRACT ADMINISTRATION							
PRE-AWARD ACTIVITIES 500 0 0 500	31.B.1 PRE-AWARD ACTIVITIES							
	PRE-AWARD ACTIVITIES			500	0	0	500	

31.B.5 PROGRESS AND COMPLETION REPORTS

U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

TIME 14:57:27

SUMMARY PAGE 25

205,737 12,547 43,109 261,393

WHITE RIVER WILDLIFE REFUGE TEST
\*\* PROJECT OWNER SUMMARY - LEVEL 6 \*\*

..... QUANTY UOM CONTRACT ESCALATN CONTNGCY TOTAL COST PROGRESS AND COMPLETION REPORTS 1,200 1,200 ------0 0 1,700 CONTRACT ADMINISTRATION 1,700 31.C BENCH MARKS AND BASELINES ...... ..... ..... ...... ...... 800 0 0 800 BENCH MARKS AND BASELINES 31.D REVIEW OF SHOP DRAWINGS 1,700 0 0 1,700 REVIEW OF SHOP DRAWINGS 31.E INSPECTION AND QUALITY ASSURANCE 31.E.1 SCHEDULE COMPLIANCE \_\_\_\_\_\_ 1,800 0 0 1,800 SCHEDULE COMPLIANCE 31.E.2 COMPLIANCE SAMPLING AND TESTING 0 0 4,500 4,500 COMPLIANCE SAMPLING AND TESTING 0 6,300 6,300 0 INSPECTION AND QUALITY ASSURANCE 31.F PROJECT OFFICE OPERATION 3,200 0 0 3,200 PROJECT OFFICE OPERATION 31.H CONTR INIT CLAIMS & LITIGATIONS 800 0 0 800 CONTR INIT CLAIMS & LITIGATIONS 31.T CONSTRUCTION PHASE LCPM 1,700 0 0 1,700 CONSTRUCTION PHASE LCPM \_\_\_\_\_\_ 16,200 0 0 16,200 SUPERVISION AND ADMINISTRATION ......

WHITE RIVER NATIONAL WILDLIFE

U.S. Army Corps of Engineers PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST \*\* PROJECT DIRECT SUMMARY - LEVEL 1 \*\*

...... ST

		QUANTITY UOM CREW ID	OUTPUTMANHOURS	LABOR	EQUIPMNT	MATERIAL	TOTAL COST UNIT CO	 ST
					(a. a			
11	LEVEES AND FLOODWALLS		4,089	45,667	68,854	45,366	159,887	
30	ENGINEERING AND DESIGN		56	29,250	400	0	29,650	
31	SUPERVISION AND ADMINISTRATI		305	15,250	685	265	16,200	
	WHITE RIVER NATIONAL WILDLIF		4,450	90,167	69,939	45,631	205,737	
ı	ESCALATN						12,547	
	SUBTOTAL						218,285	
1	CONTNGCY						43,109	
	TOTAL INCL OWNER COSTS						261,393	

TIME 14:57:27

SUMMARY PAGE 53

# U.S. Army Corps of Engineers PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT DIRECT SUMMARY - LEVEL 6 \*\*

SUMMARY PAGE 69

TIME 14:57:27

..... OUTPUTMANHOURS LABOR EQUIPMNT MATERIAL TOTAL COST UNIT COST QUANTITY UOM CREW ID 11 LEVEES AND FLOODWALLS 11.1 LEVEES 11.1.1 MOBILIZATION AND DEMOBIL 11.1.1.1 LOAD AND UNLOAD EQUIPM 22 281 354 0 635 LOAD AND UNLOAD EQ 10.00 PCS 63.54 11.1.1.2 TRANSPORT EQUIPMENT (M TRANSPORT EQUIPMEN 80 851 3,864 0 4,715 80.00 HRS 58.94 11.1.1.3 MOB & DEMOB EQPMT TO B MOB & DEMOB EQPMT 8.00 HRS 32 321 422 0 743 92.89 \*\*\*\*\*\* \*\*\*\*\*\*\* \*\*\*\*\*\*\* \*\*\*\*\*\*\*\* MOBILIZATION AND D 134 1,453 4,641 0 6,094 11.1.2 REPAIR 60" SLUICE GATES 11.1.2.B METALS 11.1.2.B.1 REMOVE EXISTING 60" REMOVE EXISTING 60 2.00 EA 32 392 528 0 919 459.71 11.1.2.B.3 CLEAN AND PAINT GATE ------CLEAN AND PAINT GA 2.00 EA 32 392 528 64 984 491.79 11.1.2.B.5 ADJUST EXISTING GATE ADJUST EXISTING GA 2.00 EA 32 392 122 0 514 256.78

# U.S. Army Corps of Engineers

TIME 14:57:27 PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

SUMMARY PAGE 70

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT DIRECT SUMMARY - LEVEL 6 \*\*

...... OUTPUTMANHOURS LABOR EQUIPMNT MATERIAL TOTAL COST UNIT COST QUANTITY UOM CREW ID 11.1.2.B.7 INSTALL 60" SLUICE G ------INSTALL 60" SLUICE 2.00 EA **16** 196 264 0 460 229.86 11.1.2.B.8 REPAIR SPALLED CONCR 4 49 17 32 98 REPAIR SPALLED CON 11.1.2.B.9 METAL WORK FOR IN-OP 16 196 82 394 672 METAL WORK FOR IN-\_\_\_\_\_ 132 1,616 1,540 490 3,646 METALS ----- ----- ------132 1,616 1,540 490 3,646 REPAIR 60" SLUICE 11.1.3 REPLACE 36" SLIDE GATE 11.1.3.B METAL WORK 11.1.3.B.1 Rem Ext 36" Slide Ga **32 395 532** 0 **927** Rem Ext 36" Slide 11.1.3.B.3 Install New 36" Slid 16 196 264 5,428 5,888 Install New 36" Sl \_\_\_\_\_ 48 591 796 5,428 6,815 METAL WORK \_\_\_\_\_ 48 591 796 5,428 6,815 REPLACE 36" SLIDE 11.1.4 ELINMINATE GATE STR & RE

11.1.4.B SITE WORK

U.S. Army Corps of Engineers

TIME 14:57:27 PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

SUMMARY PAGE 71

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT DIRECT SUMMARY - LEVEL 6 \*\*

QUANTITY UOM CREW ID OUTPUTMANHOURS LABOR EQUIPMNT MATERIAL TOTAL COST UNIT COST

							,5,7,2 6531 6	
11.1.4.B.1 (	CLEAR AND GRUB							
	CLEAR AND GRUB		31	350	960	0	1,310	
11.1.4.8.2	EXC, PL, COMPACT & G							
11 1 / 5 2 1	EVEAUATE AND DIAGE	3/35 00 07	0/	1 10/	7 ///	•	/ 5/0	4 77
	EXCAVATE AND PLACE INSTALL GEOTEXTILE	2625.00 CY	86	1,104	3,446	0	4,549	1.73
	SPREAD AND SHAPE T	3878.00 SY 2625.00 CY	4 48	42 729	1 172	8,708 0	8,762	2.26 0.72
11.1.4.B.2.4		2625.00 CY	48	695	1,172 535	0	1,901 1,231	0.72
	CHECK GRADE	2625.00 CY	10	100	57	0	157	0.06
111114.0.2.5	CHECK GRADE	2023:00 01						0.00
	EXC, PL, COMPACT &	2625.00 CY	195	2,669	5,222	8,708	16,599	6.32
	באסן ובן מסווו אסן ע	2023100 01	173	2,007	J, 444	0,700	10,377	0.52
11.1.4.B.4 H	HAUL & DUMP RIPRAP O							
	HAUL & DUMP RIPRAP	2470.00 TON	1,213	12,899	29,967	11,727	54,593	22.10
11.1.4.B.5 F	PLACE RIPRAP ON SLOP							
	D. 405 D.D. 5.	0/70 00 7-11	4 445	44 670			45 444	
	PLACE RIPRAP ON SL	2470.00 TON	1,115	11,970	3,691	0	15,661	6.34
11 1 / 20 5	COTADITOU TIME ON TO							
11.1.4.5.9	STABLISH TURF ON TO							
11 1 4 R Q 1	Replace Top Soil	17.00 CY	16	151	28	0	178	10.49
	Till or Prepare Se	871.00 SF	8	75	14	0	89	0.10
	Seed and Fertilize	97.00 SY	1	5	1	10	16	0.16
	3324 3.14 13.1611123	,, <b></b>			·			
	ESTABLISH TURF ON	871.00 SF	24	231	42	10	283	0.32
			*****					
	SITE WORK		2,579	28,119	39,882	20,446	88,447	
11.1.4.C COM	CRETE							
11.1.4.C.1 F	PREPARE CULVERT TO R							
	PREPARE CULVERT TO		4	49	23	0	72	

# U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT DIRECT SUMMARY - LEVEL 6 \*\*

SUMMARY PAGE 72

TIME 14:57:27

	** p	PROJECT DIRECT SUMMARY - LEV	EL 6 **				
	QUANTITY UOM C		LABOR	EQUIPMNT	MATERIAL	TOTAL COST	UNIT COST
11.1.4.C.3 PLACE CONC PL	UG IN C						
PLACE CONC	PLUG IN 3.14 CY	25	308	145	222	674	214.57
CONCRETE		29	357			746	
11.1.4.E METALS							
11.1.4.E.1 REMOVE EXISTI	NG GATE						
REMOVE EXIS	STING GA	16	196	264	0	460	
METALS		16		264	0	460	
ELINMINATE	GATE ST					89,652	
11.1.5 REPAIR 60' OF LEV	EE & AD						
11.1.5.B SITE WORK							
11.1.5.B.1 CLEAR AND GRU	iB						
CLEAR AND G	RUB	6	72	198	0	270	
11.1.5.B.3 EXC, PL, COMP	ACT & G						
11.1.5.B.3.1 EXCAVATE AN		5		197	0	260	1.73
11.1.5.8.3.2 INSTALL GEO		2		6	499	526	2.37
11.1.5.B.3.3 SPREAD AND 11.1.5.B.3.4 COMPACTION	SHAPE T 150.00 CY 150.00 CY	3 3	42 40	67 31	0	109 70	0.72 0.47
11.1.5.8.3.5 CHECK GRADE		1	6	3	0	9	0.06
EXC, PL, CO	MPACT & 150.00 CY	13	172	304	499	974	6.49
11.1.5.B.4 HAUL RIPRAP F	ROM QUA						
HAUL RIPRAP	FROM Q 530.00 TON	260	2,768	6,430	2,516	11,714	22.10

# U.S. Army Corps of Engineers

TIME 14:57:27

SUMMARY PAGE 73

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT DIRECT SUMMARY - LEVEL 6 \*\*

...... QUANTITY UOM CREW ID OUTPUTMANHOURS LABOR EQUIPMNT MATERIAL TOTAL COST UNIT COST 11.1.5.B.5 PLACE QUARRY RUN STO ------PLACE QUARRY RUN S 530.00 TON 239 2,569 792 0 3,360 6.34 11.1.5.B.7 ESTABLISH TURF ON LE 11.1.5.B.7.1 Replace Top Soil 213 39 0 252 10.49 24.00 CY 23 11.1.5.B.7.2 Prepare Seed Bed 1307.00 SF 0 0.10 12 113 21 134 7 1 . 15 11.1.5.B.7.3 Seeding and Fertil 145.00 SY 0.16 1 23 35 333 61 15 409 ESTABLISH TURF ON SITE WORK 554 5,913 7,785 3,030 16,727 11.1.5.C CONCRETE SPILLWAY WORK 11.1.5.C.1 PREPARE SURFACE AREA PREPARE SURFACE AR 350.00 SF 17 161 20 0 0.52 11.1.5.C.2 PLACE FORMS FOR CONC 9 87 148 PLACE FORMS FOR CO 160.00 LF 4 52 0.92 11.1.5.C.3 PLACE WWF (W6 X 6) I PLACE WWF (W6 X 6) 4 49 12 67 129 0.37 350.00 SF 11.1.5.C.4 PLACE CONCRETE IN SP 10 115 26 216 357 116.60 PLACE CONCRETE IN 3.06 CY 11.1.5.C.5 FINISH CONCRETE IN S

FINISH CONCRETE IN 350.00 SF

5 70 17 0 87

0.25

# U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT DIRECT SUMMARY - LEVEL 6 \*\*

TIME 14:57:27
SUMMARY PAGE 74

		QUANTITY UOM CREW ID	OUTPUTMANHOURS	LABOR	EQUIPMNT	MATERIAL	TOTAL COST	UNIT COS
			****************					
11.1.5.c.6	CURE CONCRETE IN SPI							
	CURE CONCRETE IN S	3.50 CSF	1	6	1	9	15	4.3
	CONCRETE SPILLWAY	3.06 CY	41	454	84	378		299.3
	REPAIR 60' OF LEVE						17,643	
11.1.6 CONST	1500 LF OF LEVEE							
11.1.6.B CON	NST 1500 LF OF LEVEE							
11.1.6.B.1 C	CLEAR AND GRUB							
	CLEAR AND GRUB	1.44 ACR	131	1,483	4,065	0	5,548	3852.5
11.1.6.B.3 C	CONST 1500 LF OF LEV							
11.1.6.B.3.2 11.1.6.B.3.3 11.1.6.B.3.4	Exc, Haul & Place Apply Geotextile M Spread, and Shape Compaction Check Grade	4400.00 CY 6500.00 SY 4400.00 CY 4400.00 CY 4400.00 CY	144 59 80 80 16		5,776 153 1,964 897 96	14,596 0	2,063	1.73 2.36 0.72 0.47
	CONST 1500 LF OF L		379	4,963		14,596		
11.1.6.B.5 E	STABLISH TURF							
	Replace and Spread Prepare Seed Bed Seeding and Fertil	1162.00 CY 62726.00 SF 6970.00 SY	17 14 14	224 150 150	699 22 22	0 0 776	923 172 948	0.79 0.00 0.14
	ESTABLISH TURF	1.44 ACR	46	524	743	776	2,043	1419.06
	CONST 1500 LF OF L		556	6,970	13,695	15,373	36,037	
	CONST 1500 LF OF L		556	6,970	13,695	15,373	36,037	
	LEVEES		4,089	45,667	68,854	45,366	159,887	
	LEVEES AND FLOODWA		4,089	45,667	68,854	45,366	159,887	

# U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT DIRECT SUMMARY - LEVEL 6 \*\*

SUMMARY PAGE 75

TIME 14:57:27

	QUANTITY UOM CREW ID	OUTPUTMANHOURS	LABOR	EQUIPMNT	MATERIAL	TOTAL COST U	INIT COS
30 ENGINEERING AND DESIGN							
30.B ENGRG & DESIGN PRIOR TO 03							
30.B.2 ENGR SUPERVISION & REVIE							
ENGR SUPERVISION &	25.00 MHR	0	1,250	0	0	1,250	50.0
30.B.4 DESIGN BY THIS DISTRICT							
DESIGN BY THIS DIS	200.00 MHR	0	10,000	0	0	10,000	50.0
30.B.7 RECONN & DETAIL PROJECT							
RECONN & DETAIL PR	40.00 MRS	0				2,000	50.0
ENGRG & DESIGN PRI		0				13,250	
O.H PLANS AND SPECIFICATIONS							
O.H.L BIDABILITY, CONSTRUCTIBI							
BIDABILITY, CONSTR	40.00 MHR	0	2,000	0	0	2,000	50.0
PLANS AND SPECIFIC		0	2,000	0	0	2,000	
O.J ENGINEERING DURING CONSTRU							
O.J.1 AE CONTR AWARD/ADMINISTR							
AE CONTR AWARD/ADM	8.00 MHR	8	400	0	0	400	50.0
0.J.3 VALUE ENGRG CH PROPOSALS							
VALUE ENGRG CH PRO	8.00 MHR	8	400	0	0	400	50.00
0.J.5 PERIODIC INSPECTIONS							

U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT DIRECT SUMMARY - LEVEL 6 \*\*

TIME 14:57:27
SUMMARY PAGE 76

	QUANTITY UOM CREW ID	OUTPUTMANHOURS	LABOR	EQUIPMNT	MATERIAL	TOTAL COST	UNIT COST
		******				********	
PERIODIC INSPECTIO	40.00 MHR	40	2,000		0	2,400	60.00
ENGINEERING DURING		56			0		
30.M COST ENGINEERING							
COST ENGINEERING	80.00 MHR	0				4,000	50.00
30.N CONST & SUPPLY CONTR AWARD							
30.N.1 PREPARATION OF BID DOCUM							
PREPARATION OF BID	16.00 MHR	0	800	0	0	800	50.00
30.N.2 CONTRACT NEGOTIATIONS							
CONTRACT NEGOTIATI	8.00 MHR	0	400	0	0	400	50.00
30.N.3 CONTRACTING OFFICE ACTIV							
CONTRACTING OFFICE	24.00 MHR	0	1,200			1,200	50.00
CONST & SUPPLY CON		0			0	2,400	
30.T PED PHASE LCPM							
PED PHASE LCPM	96.00 MHR	0	4,800	0	0	4,800	50.00
ENGINEERING AND DE		56	29,250	400	0	29,650	
31 SUPERVISION AND ADMINISTRATI							
31.B CONTRACT ADMINISTRATION							
31.B.1 PRE-AWARD ACTIVITIES							
PRE-AWARD ACTIVITI		10	500	0	0	500	
31.B.5 PROGRESS AND COMPLETION							

# U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT DIRECT SUMMARY - LEVEL 6 \*\*

SUMMARY PAGE 76

TIME 14:57:27

	QUANTITY UOM CREW ID	OUTPUTMANHOURS	LABOR	EQUIPMNT	MATERIAL	TOTAL COST	UNIT COST
PERIODIC INSPECTIO	40.00 MHR	40	2,000	400	0	2,400	60.00
ENGINEERING DURING		56	2,800	400	0	3,200	
30.M COST ENGINEERING							
COST ENGINEERING	80.00 MHR	0	4,000	0	0	4,000	50.00
30.N CONST & SUPPLY CONTR AWARD							
30.N.1 PREPARATION OF BID DOCUM							
PREPARATION OF BID	16.00 MHR		800	0	0	800	50.00
30.N.2 CONTRACT NEGOTIATIONS							
CONTRACT NEGOTIATI	8.00 MHR	0	400	0	0	400	50.00
30.N.3 CONTRACTING OFFICE ACTIV							
CONTRACTING OFFICE	24.00 MHR	0	1,200	0	0	1,200	50.00
CONST & SUPPLY CON		0	2,400	0	0	2,400	
30.T PED PHASE LCPM							
PED PHASE LCPM	96.00 MHR	0	4,800	0	0	4,800	50.00
ENGINEERING AND DE		56	29,250	400	0	29,650	
31 SUPERVISION AND ADMINISTRATI							
31.B CONTRACT ADMINISTRATION							
31.B.1 PRE-AWARD ACTIVITIES							
PRE-AWARD ACTIVITI		10	500	0	0	500	
31.B.5 PROGRESS AND COMPLETION							

WHITE RIVER NATION

### U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

TIME 14:57:27

SUMMARY PAGE 77

WHITE RIVER WILDLIFE REFUGE TEST

\*\* PROJECT DIRECT SUMMARY - LEVEL 6 \*\*

	QUANTITY UOM CREW ID	OUTPUTMANHOURS	LABOR	EQUIPMNT	MATERIAL	TOTAL COST UNIT
PROGRESS AND COMPL		24	1,200	0	0	1,200
CONTRACT ADMINISTR		34	1,700	0	0	1,700
1.C BENCH MARKS AND BASELINES						
BENCH MARKS AND BA		15	750	35	15	800
1.D REVIEW OF SHOP DRAWINGS						
REVIEW OF SHOP DRA		34	1,700	0	0	1,700
1.E INSPECTION AND QUALITY ASS						
1.E.1 SCHEDULE COMPLIANCE						
SCHEDULE COMPLIANC		36	1,800	0	0	1,800
1.E.2 COMPLIANCE SAMPLING AND						
COMPLIANCE SAMPLIN		80	4,000			4,500
INSPECTION AND QUA		116	5,800			6,300
1.F PROJECT OFFICE OPERATION						
PROJECT OFFICE OPE		56	2,800	200	200	3,200
1.H CONTR INIT CLAIMS & LITIGA						
CONTR INIT CLAIMS		16	800	0	0	800
1.T CONSTRUCTION PHASE LCPM						
CONSTRUCTION PHASE		34	1,700	0	0	
SUPERVISION AND AD		305	15,250	685	265	16,200

4,450 90,167 69,939 45,631 205,737

Fri 29 Mar 1991

U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\*\* PROJECT DIRECT SUMMARY - LEVEL 6 \*\*\*

QUANTITY UOM CREW ID

QUANTITY UOM CREW ID

OUTPUTMANHOURS

LABOR EQUIPMNT MATERIAL TOTAL COST UNIT COST

\*\*\*

SUBTOTAL

SUBTOTAL

CONTNGCY

218,285

CONTNGCY

TOTAL INCL OWNER COSTS

-----

261,393

### U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\* CONTRACTOR INDIRECT SUMMARY - LEVEL 1 \*\*

QUANTY UOM DIRECT OVERHEAD HOME OFC PROFIT BOND TOTAL COST UNIT

11. LEVEES AND FLOODWALLS A PRIME CONTRACTOR

124,600 12,460 6,853 14,391 1,583 159,887

TIME 14:57:27

SUMMARY PAGE 80

30. ENGINEERING AND DESIGN NOT IDENTIFIED

31. SUPERVISION AND ADMINISTRATION NOT IDENTIFIED

### U.S. Army Corps of Engineers

# PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST

\*\* CONTRACTOR INDIRECT SUMMARY - LEVEL 6 \*\*

SUMMARY PAGE 87

TIME 14:57:27

		OVERHEAD			BOND	TOTAL COST	UNIT
11.1.4.B.2.1. EXCAVATE AND PLACE NEW FILL MAT							
A PRIME CONTRACTOR		355	195	409	45	4,549	
11.1.4.B.2.2. INSTALL GEOTEXTILE MATERIAL							
A PRIME CONTRACTOR	6,828	683	376	789	87	8,762	
11.1.4.B.2.3. SPREAD AND SHAPE TO GRADE							
A PRIME CONTRACTOR	1,48	148	81	171	19	1,901	
11.1.4.B.2.4. COMPACTION							
A PRIME CONTRACTOR	959	96	53	111	12	1,231	
11.1.4.B.2.5. CHECK GRADE							
A PRIME CONTRACTOR	122	12	7	14	2	157	
11.1.4.B.9.1. Replace Top Soil							
A PRIME CONTRACTOR	139	14	8	16	2	178	
11.1.4.B.9.2. Till or Prepare Seedbed							
A PRIME CONTRACTOR	69	7	4	8	1	89	
1.1.4.B.9.3. Seed and Fertilize							
A PRIME CONTRACTOR	12	1	1	1	0	16	
11.1.5.B.3.1. EXCAVATE AND PLACE FILL MATERIA	L						
A PRIME CONTRACTOR	203	20	11	23	3	260	
11.1.5.B.3.2. INSTALL GEOTEXTILE MATERIAL							
A PRIME CONTRACTOR	410	41	23	47	5	526	
11.1.5.B.3.3. SPREAD AND SHAPE TO GRADE							
A PRIME CONTRACTOR	85	8	5	10	1	109	
11.1.5.B.3.4. COMPACTION							
A PRIME CONTRACTOR	55	5	3	6	1	70	
11.1.5.B.3.5. CHECK GRADE							
A PRIME CONTRACTOR	7	1	0	1	0	9	
11.1.5.B.7.1. Replace Top Soil							
A PRIME CONTRACTOR	196	20	11	23	2	252	
1.1.5.B.7.2. Prepare Seed Bed							
A PRIME CONTRACTOR	104	10	6	12	1	134	
1.1.5.B.7.3. Seeding and Fertilizer							
A PRIME CONTRACTOR	18	2	1	2	0	23	
1.1.6.B.3.1. Exc, Haul & Place fill							
,							

U.S. Army Corps of Engineers

PROJECT WRRFGH: WHITE RIVER NATIONAL WILDLIFE - REFUGE, REHABILITATION OF

WHITE RIVER WILDLIFE REFUGE TEST


\*\* CONTRACTOR INDIRECT SUMMARY - LEVEL 6 \*\*

TIME 14:57:27
SUMMARY PAGE 88

		MOU YTMAUD	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT
A	PRIME CONTRACTOR		5,942	594	327	686	75	7,625	
11.1.6.B.	3.2. Apply Geotextile Material								
Α	PRIME CONTRACTOR		11,930	1,193	656	1,378	152	15,309	
11.1.6.B.	3.3. Spread, and Shape to Grade								
Α	PRIME CONTRACTOR		2,483	248	137	287	32	3,186	
11.1.6.B.	3.4. Compaction								
Α	PRIME CONTRACTOR		1,607	161	88	186	20	2,063	
11.1.6.B.	3.5. Check Grade								
А	PRIME CONTRACTOR		205	21	11	24	3	263	
11.1.6.B.	5.1. Replace and Spread Top Soil								
Α	PRIME CONTRACTOR		719	72	40	83	9	923	
11.1.6.B.	5.2. Prepare Seed Bed								
Α	PRIME CONTRACTOR		134	13	7	15	2	172	
11.1.6.B.	5.3. Seeding and Fertilizing								
А	PRIME CONTRACTOR		739	74	41	85	9	948	

# ATTACHMENT D

# **Referenced Drawings**



Forterra's Crown-Span units are rectangular three-sided reinforced concrete structures designed to be installed on cast-inplace concrete footings. Crown-Span units are produced with spans from 16 to 40 feet for prestressed units and 16 to 20 feet for non-prestressed. Risers are available up to 12 feet. Installations can be single or multiple cells. The units can be skewed up to 43 degrees to accommodate streambed alignment.

Crown-Span units are recommended where natural stream bottoms are desired, wetlands must be spanned, the span is longer than can be accommodated with a precast box culvert and when cost and time of construction are critical.

Forterra's engineers design the cast-in-place footings based on soil bearing data provided by the owner. The precast sections are designed for each specific application according to AASHTO2 Standard Specifications for Highway Bridges.


Typical applications include new or replacement highway bridges, storm drains, stormwater management structures, culverts, culvert extensions and utility or pedestrian tunnels.


Connections are provided for attaching guard rails, parapets and wing walls. Individual sections are typically eight feet long and are butted against adjacent units. The joints are sealed with an external wrapper.


Forterra's Crown-Span units have been used successfully for over a decade by state DOT's, municipalities and private developers.


TITLE	PLANT	STATE	SECTION.PAGE	DATE
Typical Crown-Span Unit		AR	8.1	2-1-05


















NAME		STAKIN	IG SHE	ET		PRI.		<u> ککد عح</u>	E 350 KIND: MCM 25 KV DESIGN TENSION UC TWP. RG. SEC.							•	_ STA								
	AR		<u></u>			REDE	REMENT								NOW				MAP DE						RE
TYPE (EX)	POLE	SPAN	7 POLES	1	UNIT	R/W	<del></del>	RANS.	T	1	GUY		т	ICHOR		ECONDA	H.O Y	NIT	SER	ACE C	LH. JINIT	SECO		BURIED UNIT	_ SEC. OF
(LN,H) (NEW)	NUMBER		H. & C.	<del></del>	U.R.D.	CLEARING		"UG"	CR.		UNIT	LEAD	NO.	UNIT	_		NO.	OR K.	SPAN	NO.	OF:	SPAN	NO.	UK OR UM	WIRE
	A = A	2400	2)45-2		UCH+				2) -1	/															
																							ļ		<u> </u>
New	STA 1211480				umb-6																				
New	S T A 1223+80	2400	2)45-2		uc H				2)-1											-					
																				-					
New	STA 1235+80	)			um6-6																				
																								!	
NOTES	<u>}</u>			Ts	KETCH (	OF WORK	•															- 1 1		100	NSTRUC
	•				Str. Str. 25				<b>v</b> Dr	ഹ				5	10 ta 180	5ti 215ti EM 05 97a	4 190 <u>4</u> vel		51 <sup>1</sup> 223.		235	5+A 5+80	•]   	PRI PRI SEG	I. O.H. I. BURIE C. O.H. C. BURIE TIREMEN
		N		11/	ENE 08 CO ENE	4		8	1991	180 				12111		<i>↓</i>	. –		12 <b>3</b> 3.	3	ر رئے۔۔۔			PRI SEI	I. BURIE R. O.H. R. BURI

gravel Rd






- 1. TOTAL ARRESTER LEAD LENGTH MUST BE UNDER 3'.
- 2. NO BENDS PERMITTED WITHIN 6" OF CABLE TERMINAL BASE.
- 3. ALLOW MINIMMUM CABLE SLACK OF 24" AT BOTTOM OF
- 4. ALL LIVE PARTS MUST HAVE AN 18 FOOT CLEARANCE ABOVE GROUND.

5.	Clearance	e to s	groui	nded	equip	ment	or to	expos
	primary around.	cable	to I	be no	less	than	15 (	lbove
	arouna.							

ITEM	NO.	MATERIAL	ITEM	NO.	MATERIAL
d	16		sb	3	Switch, disconnect and hardware
q	4	Crossarm, 4 5/8" x 5 5/8" x 12'-0"	αv		Jumpers, as required
i	14	Bolt, carriage, 1/2" x req'd length	cj		#4 HD copper, as required
i		Screw, lag, as reg'd	Uce	6	Arrester
'n	6	Bolt, double arming, 5/8" x req'd. Igth.	Ugc		Conduit, size & length as required
р		Connectors, as required	Ugk	8	Cable termination
bo	4	Shackle, anchor	Uhc	8	Cable support
dg	4	Eye screw, or drive hook			Conduit straps, as req'd
ek	16	Locknuts, 5/8"		12	Conduit, 2-hole pad and hardware

2-POLE 3-PHASE CABLE TERMINAL POLES WITH HOOK-OPERATED DISCONNECT SWITCHES

LEDBETTER, TOTH, & ASSOCIATES CONSULTING ENGINEERS										
DRAWN BY: PGP	DATE:	10-13-9	7							
CHECKED BY: MAJ	FILE:	MIS_324	4 - 4 - 4 - 4 - 4 - 4 - 4 - 4 - 4 - 4 -							
APPROVED BY: MDB	No.:	UCH								



NOTE:

BACKFILL SHALL BE COMPACTED IN 8 INCH LIFTS.

LEGEND


UNDISTRIBUTED EARTH

SAND OR CLEAN SOIL

COMPACTED BACKFILL UNLESS OTHERWISE SPECIFIED

TRENCHES FOR DIRECT BURIAL CABLES

LEDBETTER, TOTH, & ASSOCIATES CONSULTING ENGINEERS					
DRAWN BY: PGP	DATE: 10-13-97				
CHECKED BY: MAJ	FILE: MIS_294				
APPROVED BY: MDB	No.: UR2-1A				



**BRIDGE PLAN** 

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.


If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.



9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069 800-338-1122 513-645-7000 513-645-7993 FAX



PROJECT No.:	SEQ. No.:		DATE:		
212251			10/17/2017		
DESIGNED:		DRAW	VN:		
DYOB			DYOB		
CHECKED:		APPR	OVED	:	
DYOB			DY	ОВ	
SHEET NO.:					
	1	OI	F	5	



# **CROSS SECTION**

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.


If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.



9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069 800-338-1122 513-645-7000 513-645-7993 FAX



PROJECT No.:	SEQ. No.:		DATE:		
212251			10/17/2017		
DESIGNED:		DRAW	VN:		
DYOB			DYOB		
CHECKED:		APPR	OVED:		
DYOB			DYOB		
SHEET NO.:					
	2	OI	ғ 5		



# **UPSTREAM END ELEVATION**

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.


If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.



9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069 800-338-1122 513-645-7000 513-645-7993 FAX



PROJECT No.:	SEQ. No.:		DATE:		
212251			10/17	7/2017	
DESIGNED:		DRAW	VN:		
DYOB			DYOB		
CHECKED:	APPR		OVED:		
DYOB			DYO	В	
SHEET NO.:					
	3	OI	- ;	5	



# **DOWNSTREAM END ELEVATION**

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.




9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069 800-338-1122 513-645-7000 513-645-7993 FAX



PROJECT No.:	SEQ. No.:		DATE:	
212251			10/	17/2017
DESIGNED:		DRAW	/N:	
DYOB			DY	OB
CHECKED:		APPR	OVED	:
DYOB		DYOB		
SHEET NO.:				
	4	OI	F	5


# DRAWING ONL

# **EXPRESS FOUNDATIONS**





# **EXPRESS FOUNDATIONS**



The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

REINFORCING BAR (TYP.)

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

**ENGINEERED SOLUTIONS LLC** www.ContechES.com

9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069 513-645-7000



PROJECT No.:	SEQ. No.:		DATE:		
212251			10	/17/20	17
DESIGNED:		DRAW	/N:		
DYOB			DY	OB	
CHECKED:		APPR	OVED	):	
DYOB			DY	OB	
SHEET NO.:					
	5	OI	F	5	